

Appendix A

HDR Site Assessment Report (October 24, 2019)

> Preliminary Design Report Version - Final

FSS

Memo

Date:	Thursday, October 24, 2019
Project:	Climate Adaptive Design (CAD) Studio – Piermont Living Shoreline Project
Prepared By:	HDR Engineering
Subject:	Site Assessment Report
Site Visit Participants:	HDR: David S. Davis, Dave Yozzo, Steve Seymour, Kevin Verweire, Casey Stokes, James Eberhardt, Zak Lehmann with Daniel Miller (NYSDEC-HRNERR) and Nathan Mitchell (Piermont Waterfront Resiliency Commission)

PURPOSE AND INTENT

HDR conducted a site investigation of the proposed Piermont living shoreline project ("Project") area on September 23, 2019 and on October 4, 2019 [unmanned aerial system (drone) survey only]. Prior to the site assessment a qualitative review of each of the five original Climate Adaptive Design (CAD) Studio concepts and input from the stakeholder engagement process were used to identify the potential project area located in the northwest corner of the existing Piermont Pier adjacent to and centered on the water-ward side of Flywheel Park and Parelli Park in the Village of Piermont, New York (**Figure 1**). The site assessment was intended to gather aerial drone, topographic, and ecological data to be used for the development of the preliminary design of a living shoreline feature that will meet the goals and objectives of the Project.

An ecological functional assessment was conducted to document the level to which the proposed Project area was performing NYSDEC-cited (Part 661.2; Tidal Wetlands – Land Use Regulations) functions and values for tidal wetlands and adjacent areas. By assessing the current ability of the Project area to perform these functions and values, goals may be set to improve or enhance functions through the living shoreline project design.

In addition, a reference shoreline was surveyed at the southeast end of Piermont Pier (reference site) on September 23, 2019. The objective of the reference site survey was to record the elevation of substrate and shoreline vegetation communities along transects perpendicular to the shore. The data collected from the reference site will be used during the development of the

preliminary design to design target plant communities and aid in the understanding of local tidal datums.

Site Assessment Activities

The following activities were conducted during the site assessment in accordance with the approved Quality Assurance Project Plan (QAPP), Version 1 dated August 13, 2019:

- 1: General assessment of existing shoreline features and condition.
- 2: Ecological assessment of existing ecological communities and functions at the site, with emphasis on dominant plant species; invasive species present; rare plants or animals; wildlife species observed; dominant substrate types, bank and shoreline stability, and observed site constraints/opportunities.
- 3: Topographic mapping measure and record three-dimensional locations of both natural and man-made elements within the Project area and reference shoreline, and graphically represent the site's existing conditions in a plan-view map.
- 4: Collection of aerial imagery, videography, and photogrammetry using a DJI Phantom 4 RTK unmanned aerial system (UAS) platform.

General Site Description

Under NYSDEC Article 25, the regulated tidal wetlands adjacent area can extend up to 300 feet landward of the wetland edge. Bulkheads, riprap, and roadways running parallel to the wetland edge (and lawfully existing prior to 1977) can limit the extent of NYSDEC's tidal wetlands jurisdiction. Virtually the entire upland in the Project area has been developed; consisting of condominiums, single-family residences, parkland, paved parking areas, walking paths, lawns, and gardens. This developed area is located upgradient of a bulkhead that runs west to east along the north shore of Piermont Pier. Vegetation in the upland is dominated by invasive species such as common reed, mugwort, Japanese knotweed, Asian bittersweet, porcelain berry, black locust, and tree-of-heaven.

The intertidal area is unvegetated; near the overlook area the substrate consists of sand, fine gravel, cobbles, cinders, and glass. Sand is predominant at the upper tidal limits and finer grained material increased from east to west along the shoreline. The intertidal community area near the overlook area is best described by the "Marine Intertidal Gravel/Sand Beach" in Edinger (2014). HDR crews found several inches of very soft organic material over the gravel and cobbles in the subtidal shallows. A concrete bulkhead ranging from 7.3 to 8 ft. in height runs along the entire east-west shore of the Project area; there is one 30" diameter metal pipe embedded in and flush with the concrete wall. The pipe is fully exposed at low water; a metal grating over the pipe is partially dislodged. The foot of the concrete wall is exposed at low tide; the intertidal area

FX

consists of cobbles with some larger boulders along the bulkhead face. There are large, discontinuous pieces of concrete, rock, and asphalt rubble in the "elbow" of the project area; some tidally stranded logs and woody debris are also present. A photographic log of key features observed during the site assessment is included as Attachment A of this report. The intertidal area at the foot of the bulkhead is best described by Edinger as the "Estuarine Riprap/Artificial Shore".

A Village of Piermont representative (Nathan Mitchell) indicated that an existing low area immediately north of the radio/siren tower serves as a conduit for storm surge into the adjacent paved parking area. He also said there is a check valve on the stormwater drain which closes at high tide to prevent surcharging via the drain. There are nearby street signs in Piermont citing the location as a "flood prone area."

In preparation for the site survey, estimates of the tidal datums were retrieved for the Project area using the NOAA Vdatum online tool on August 14, 2019. The values are shown in Table 1 below.

Table 1. Estimated Tidal Datum Elevations computed using NOAA Vdatum Online Tool. Retrieved 8/14/19.

Location	
Lat	41.042833
Lon	-73.913702
Tidal Datum	Elevation (NAVD88, US-feet)
MLLW	-1.894
MLW	-1.73
LMSL	0.113
MTL	0.008
MHW	1.841

Based on NOAA topobathymetry data available from 2018, intertidal areas (MHHW to MLLW) down to an elevation of -2 feet (NAVD88) generally extend from approximately 25 to 75 feet riverward along the shoreline with the greatest extents occurring adjacent to Parelli Park and near the public kayak launch (**Figure 1**). Beyond the Mean Lower Low Water (MLLW) mark, project area bathymetry generally ranged from -4 to -6 feet within the Project area. Elevations recorded along shoreline transects and in upland areas during the field survey will be used during the development of the preliminary design to confirm the general bathymetric and topographic conditions.

2.125

MHHW

FSS

Ecological Assessment

HDR ecologists walked the perimeter of the proposed Project area, documenting existing habitats and general site conditions, along with surrounding land use. HDR staff were accompanied by Dan Miller (NYSDEC-HRNERR) and Nathan Mitchell (Piermont Waterfront Resiliency Commission) for a portion of the site assessment. A variety of native and non-native plant species were documented in the supra-tidal and terrestrial environments above and adjacent to the site; however aquatic/intertidal vegetation was noticeably absent in the vicinity of the project area, possibly due to hydrodynamic (wind/wave) conditions and substrate type. Non-native species present above the shore zone included Japanese knotweed, mugwort, and tree-of-heaven. The dominant substrate type in the study area was cobble/gravel, with a gradation to coarse sand/gravel to the northwest, approaching the nearby marina. Estuarine organisms noted in the tidal shallows and intertidal zone included schools of juvenile Atlantic menhaden (a.k.a. "peanut bunker"), and blue crabs (both live animals, carcasses, and carapace sheds present). Atlantic rangia clam shells were abundant along the shore and in shallow water areas. A few small ribbed mussel shells were observed, but no live mussels were present in the intertidal zone. A single American eel was observed in a tide pool under a rock in the intertidal zone. Both aquatic and terrestrial/arboreal bird species were present; consisting of great blue heron, American crow, mallard, Canada goose, double-crested cormorant, rough-winged swallow, house sparrow, goldfinch, blue jay, mourning dove, Carolina wren, European starling, and ring-billed gull. No state or federally-listed rare plant or animal species were observed during the site assessment.

HDR also examined the reference shoreline on the south side of Piermont Pier. The upper intertidal area was predominantly sand, the lower intertidal area was soft peat. There was a distinct break along the shoreline where sand deposition was occurring to the east, and erosion of the peat mat was occurring to the west. Vegetation in the peat mat area was a common reed monoculture; there were several small patches of saltmarsh cordgrass associated with coarse rip rap to the east.

Functional Assessment

A summary of the NYSDEC-cited tidal wetland functions and values and observations with regard to the Project Area's current value for each function is presented below:

Wildlife Habitat – Bird use of the intertidal area and upland were noted; 13 bird species were observed during the walk-over. Blue heron, mallard, Canada geese, and gulls were observed in the intertidal area or nearby offshore waters. Schools of small menhaden and blue crabs were observed in the nearshore shallows, shells of rangia clams, ribbed mussel, and American oyster (few) were also observed.

Recreation – numerous walkers, joggers, dog walkers, and people pushing strollers were observed on the walkways and paths in the upland areas. There is an existing launch ramp for the Piermont Rowing Club for kayak and canoe launching. The nearshore waters are too shallow

for any motorized craft. No evidence of fishing was observed in the Project Area. Fishing is focused in the deeper waters to the east toward the end of Piermont Pier.

Flood, Storm and Hurricane Control – the vertical concrete bulkhead deflects waves but does not absorb wave energy. The east-west shoreline does attenuate and absorb some wave energy; but sufficient energy is apparently present to preclude intertidal plant growth.

Marine Food Production – is limited by the lack of intertidal vegetation. Use of the shallows by forage fish does contribute to the food base for larger fish and fish-eating birds.

Education and Research – Knowledge gained during the current project will contribute to restoration efforts elsewhere along the tidal Hudson River. Site is in close proximity to the Piermont Marsh component of the Hudson River National Estuarine Research Reserve (HRNERR), The Beacon Institute maintains a River and Estuary Observatory Network monitoring station at the east end of the Piermont pier and the Lamont Doherty Earth Observatory (LDEO) recently established a Hudson River Field Station on the pier.

Open Space – Parelli Park and walkways provide access to the Hudson River waterfront. Benches in the park were being used during the site visit.

Aesthetic Appreciation – The Project area provides views of the Hudson River and the Governor Mario Cuomo Bridge. A community garden is present to the west, as well as wildflower plantings.

Ecosystem Cleansing – is limited due to the lack of intertidal or subtidal vegetation. There is also no functional transition area between the upland and the intertidal area, much of the tidal range is on vertical or near-vertical surfaces in the Project Area, such as the concrete bulkhead, rip-rap, and timber cribbing backfilled with coarse rock.

Sediment/Toxicant Retention – retention of organic material is limited due to tidal flushing, lack of intertidal and subtidal vegetation, and predominantly coarse sediments.

Topographic Survey

A topographic survey was completed for the area including the existing seawall along the northern shore of the pier/condominium development, Flywheel Park, the parking area to the west of the Project area, and the overlook area near the River. The study team also visited the reference shoreline site along the southern shoreline of the pier to assess intertidal vegetation communities (both invasive common reed as well as small patches of native saltmarsh cordgrass), and substrate conditions at a small cove which may provide essential bio-"benchmarking" or reference data for the design of the living shoreline habitat mosaic. Elevation data was collected using an EOS Arrow Gold high accuracy real-time kinematic (RTK) Global Navigation Satellite System (GNSS). Points were recorded across pre-selected transects spanning the topographic profile from the pier into the Hudson River. Ground surface shots (latitude, longitude, and

elevation) were collected along transects run approximately every 50 feet perpendicular to the shoreline, and transects extended to the maximum safe wading depth out into the River. In addition, opportunistic spot elevations were recorded at various natural and man-made points of interest within the park, the adjacent community garden, and the parking lot. Finally, elevations corresponding to specific vegetation communities and shoreline features (e.g., eroding peat reefs, sand deposits, wrack line, MLW, etc.) were also recorded along two survey transects at the reference shoreline located on the southern shore of the Pier (**Figure 2**). See also Attachment B for a complete listing of all of the points that were collected.

Following the site visit, estimates of the tidal datums were retrieved for the reference site using the NOAA Vdatum online tool on October 1, 2019. The values are shown in Table 2 below.

Location	
Lat	41.042097
Lon	-73.90446
Tidal Datum	Elevation (NAVD88, US-feet)
MLLW	-1.92
MLW	-1.753
LMSL	0.111
MTL	0.008
MHW	1.848
MHHW	2.13

Table 2. Estimated Tidal Datum Elevations computed using NOAA Vdatum Online Tool. Retrieved 10/1/19.

The estimated tidal datum elevations were plotted along with elevation, substrate, and vegetation data collected at two transects (PLS-REF-T1 and PLS-REF-T2) at the reference site (**Figure 3** and **Figure 4**). These figures show *Spartina alterniflora* occurring between estimated MTL and MHW elevations, with *Phragmites australis* occurring above estimated MHW elevation, as expected for these species.

Aerial Imagery (Drone) Survey

The proposed drone flights could not be completed on September 23, 2019 because of airspace restrictions in effect related to activities at the United Nations. However, all ground control points were established and surveyed during the site visit. A second site visit including the drone survey was completed on October 4, 2019. Aerial still imagery, videos, and a photogrammetry survey were completed for the Project and adjacent areas during multiple drone flights. Following the drone survey, a 2D orthometric aerial photo was created and is shown in **Figure 2**. A preliminary digital surface model and point cloud were created for the Project site, and these models will be

reviewed further along with the on-the-ground topographic survey data during development of the preliminary design.

Engineering Summary

During the site visit, a number of subtidal and intertidal shoreline features and potential engineered solutions for the existing bulkhead were discussed with the Project partners. These features will be evaluated during the development of the preliminary design and the site-specific information collected during the site assessment will be used to inform the design. The following are some preliminary notes of those discussions and are not intended to be all inclusive of the potential features that will be considered for the design.

Subtidal Areas

Given the existing shallow water bathymetry, current recreational uses of the Project area and potential visual concerns from nearby property owners and park users, a variety of submerged aquatic habitat enhancement features were discussed including the use of concrete "reef balls" and "oyster castles." The idea of using a variety of features installed in an aggregated, nature-like non-linear manner were discussed. Given the uncertainty of biological success and potential permitting challenges, live oysters would likely not be transplanted but habitat for recruitment by native, local oysters (via natural reefs present in the vicinity of the GMC Bridge) could be created. Habitat enhancement for other, native suspension-feeding invertebrates such as ribbed mussels should be considered, and the design of the habitat structures should be optimized for use by a variety of resident, as well as transient/migratory species. Recreational access through the project area for kayaks and similar non-motorized recreational vessels should be maintained in the placement of habitat enhancement structures. The concept of using subtidal structures for the creation of aquatic habitat and enhancing recreational opportunities was considered in several of the original CAD concepts including Piermont Nexus and Piermont: The New Beginning.

Intertidal Shoreline

Opportunities for vegetated marsh plantings would likely focus on existing sandy substrate areas along the existing viewing area adjacent to Parelli Park and potentially into an area of privately owned shoreline to the north of the site. Plant species selection, substrate type and planting elevation ranges may be optimized based on bio-benchmarking data gathered from the reference shoreline site to the south of the pier and east of the Piermont Marsh reserve. The concept of using intertidal shoreline plantings to promote resiliency and habitat enhancement was considered in all of the original CAD concepts including most prominently in Re-Appearing Piermont and Piermont: The New Beginning.

Bulkheaded and Upland Areas

Educational signage describing the purpose and benefit of living shorelines could be placed along the existing viewing area in Parelli Park and potentially in Flywheel Park. Opportunities for

FX

restoring, moving or incorporating the existing fire whistle/cell tower should be considered (note that a separate Piermont Lighthouse project is also considering this). Upland (coastal meadow) plantings and opportunities for increased water retention in Parelli Park could be considered. The existing kayak launch is being replaced within its existing same footprint and should be incorporated into the preliminary design. The concept of restoring the existing concrete and boulder bulkhead along Flywheel Park was also discussed by creating a more sloping revetment that could be planted with vegetation and by acquiring the existing paved pathway, and potentially moving the existing gazebo to the south. The concept of improving bulkheaded and upland areas to promote resiliency as well as promoting educational components was included in all of the original CAD concepts including most prominently in Evolve/Connect/Redefine, Cultural-Led Adaptation and Piermont: The New Beginning.

Restoration Constraints

Several potential design constraints were identified in the Project area. The elevation difference between the existing intertidal area and crest of the concrete bulkhead will require any change in the shoreline repose (revetment) to extend into the tidal Hudson or further to the south with a lowering of the current upland area. The current use of the adjacent upland as either a park, active roadway, or walking path may preclude any re-contouring to increase the width of the tidally affected area while maintaining the existing walkway elevation. However, the design could consider either an elevated walkway or a lower elevation walkway through the shoreline stabilization area. Preservation of the existing canoe/kayak launch in its current location may also limit the extent of plantings and shoreline stabilization measures. The potential effects of stormdriven tides on living shoreline features will need to be considered; storm tides at high water can cause flooding; storm tides at low water can erode or displace features in the tidal shallows.

Based on the results of this site assessment and ongoing stakeholder engagement, specific project features that consider these restoration constraints will be developed as part of the preliminary conceptual design for the living shoreline project. The overarching project goals for the project remain:

- Protect and stabilize the existing shoreline north of the Piermont Pier and East of Parelli Park;
- 2. Develop intertidal and subtidal habitat features to benefit fish, shellfish and other wildlife within the project area;
- 3. Maintain and enhance recreational access to the river and its shoreline habitats while including educational and interpretive elements that effectively engage the public.



(FIGURE 1)

Figure 1. Project Study Area, Transect Locations, and Topobathymetry.

ACTIVEPROJECT50300101774150.0 GIS_MODELSI7.2 WIPMAP_DOCS/DRAFT/PLS_PROJECT_BATHY_20101015.MXD + USER_FBRILHAN + DATE: 10/15/2018

FS





FSS




Figure 3. Survey Transect PLS-REF-T1

FSS



Figure 4. Survey Transect PLS-REF-T2

FX

Attachment A

Site Assessment Photo Log


PIERMONT LIVING SHORELINE PROJECT

SITE ASSESSMENT 9-23-19

GENERAL SITE AND SHORELINE FEATURES



























SITE ASSESSMENT ACTIVITY















REPRESENTATIVE BIOTA





REFERENCE SITE – SOUTH SHORE OF PIER













UAS (Drone) Survey – 10-4-2019









FX

Attachment B

Survey Datasheet

SURVEY DATASHEET

Location:		Pierm	nont, New York	Project Name:	Piermont CAD-Living Shoreline
Date:	9/23/2019	Observers:	Verweire, Stokes, Lehmann, Eberhardt	Project Number:	N/A
Weather:	Partly cloudy, no rai	nfall in the past 3 days, high	temp in the mid 80s°F, predicted low water at 11:37 a.m.	Notes:	See comments field
Start Time:	9:00	Stop Time:	15:00		

TransectID	Name	PointType	DomSubstrate	WaterDepth	Comments	POINT_X	POINT_Y	ElevNAVD88, ft	GNSS Fix DateTime (GMT)
PLS-T1	PLS-T1-1	General Ground	Sand - Medium			-73.9161514	41.0427562	1.43	2019-09-23 15:01
PLS-T1	PLS-T1-2	General Ground			transition	-73.9161343	41.0427636	0.68	2019-09-23 15:02
PLS-T1	PLS-T1-3	General Ground			transition substrate	-73.9161398	41.0427693	0.76	2019-09-23 15:02
PLS-T1	PLS-T1-4	General Ground	Gravel - Medium			-73.9161236	41.0427786	0.00	2019-09-23 15:02
PLS-T1	PLS-T1-5	General Ground	Gravel - Medium		wsel	-73.9161006	41.0427917	-1.25	2019-09-23 15:03
PLS-T1	PLS-T1-6	General Ground			transition of substrate	-73.9160947	41.0428052	-1.61	2019-09-23 15:04
PLS-T1	PLS-T1-7	General Ground	Silt/Clay			-73.916037	41.0428494	-2.24	2019-09-23 15:05
PLS-T1	PLS-T1-8	General Ground	Silt/Clay			-73.9159990	41.0428793	-2.32	2019-09-23 15:05
PLS-T2	PLS-T2-1	General Ground			transition	-73.9160970	41.0426782	1.87	2019-09-23 15:07
PLS-T2	PLS-T2-2	General Ground			transition	-73.9160950	41.0426747	1.85	2019-09-23 15:08
PLS-T2	PLS-T2-3	General Ground	Gravel - Fine			-73.9160893	41.0426782	1.59	2019-09-23 15:08
PLS-T2	PLS-T2-4	General Ground			transition	-73.9160840	41.0426812	1.38	2019-09-23 15:09
PLS-T2	PLS-T2-5	General Ground	Gravel - Coarse			-73.9160722	. 41.0426910	0.83	2019-09-23 15:09
PLS-T2	PLS-T2-6	General Ground			transition	-73.9160599	41.0426995	0.22	2019-09-23 15:10
PLS-T2	PLS-T2-7	General Ground	Gravel - Fine			-73.9160527	41.0427040	-0.13	2019-09-23 15:10
PLS-T2	PLS-T2-8	General Ground			transition	-73.9160454	41.0427075	-0.45	2019-09-23 15:10
PLS-T2	PLS-T2-9	General Ground	Gravel - Coarse		wsel	-73.9160317	41.0427156	-1.26	2019-09-23 15:10
PLS-T2	PLS-T2-10	General Ground			transition	-73.9160172	. 41.0427334	-1.85	2019-09-23 15:11
PLS-T2	PLS-T2-11	General Ground	Silt/Clay			-73.9159608	41.0427795	-2.52	2019-09-23 15:11
PLS-T2	PLS-T2-12	General Ground	Silt/Clay			-73.9159076	41.0428242	-2.52	2019-09-23 15:12
PLS-T3	PLS-T3-1	General Ground	Sand - Medium			-73.9160083	41.0425512	3.29	2019-09-23 15:13
PLS-T3	PLS-T3-2	General Ground			transition	-73.9159842	41.0425682	1.85	2019-09-23 15:14
PLS-T3	PLS-T3-3	General Ground	Gravel - Fine			-73.9159817	41.0425693	1.73	2019-09-23 15:14
PLS-T3	PLS-T3-4	General Ground			transition	-73.9159783	. 41.0425726	1.56	2019-09-23 15:14
PLS-T3	PLS-T3-5	General Ground	Gravel - Coarse			-73.9159583	41.0425865	0.70	2019-09-23 15:14
PLS-T3	PLS-T3-6	General Ground			transition	-73.9159315	41.0426048	-0.84	2019-09-23 15:15
PLS-T3	PLS-T3-7	General Ground	Cobble - Small		wsel	-73.9159122	. 41.0426267	-1.32	2019-09-23 15:15
PLS-T3	PLS-T3-8	General Ground	Cobble - Small			-73.9158450	41.0426847	-1.85	2019-09-23 15:16
PLS-T3	PLS-T3-9	General Ground	Cobble - Small			-73.9157768	41.0427259	-2.33	2019-09-23 15:16
PLS-T4	PLS-T4-1	General Ground	Gravel - Coarse			-73.9158669	41.0424482	2.49	2019-09-23 15:18
PLS-T4	PLS-T4-2	General Ground			transition	-73.9158359	41.0424787	0.56	2019-09-23 15:18
PLS-T4	PLS-T4-3	General Ground	Cobble - Small			-73.9157808	41.0425325	-0.64	2019-09-23 15:19
PLS-T4	PLS-T4-4	General Ground	Cobble - Small		wsel	-73.915707	41.0425815	-1.34	2019-09-23 15:20
PLS-T4	PLS-T4-5	General Ground	Cobble - Small			-73.9156487	41.0426350	-2.20	2019-09-23 15:20
PLS-T5	PLS-T5-1	General Ground	Boulder - Large/Vry Large			-73.9156982	41.0423922	3.57	2019-09-23 15:21
PLS-T5	PLS-T5-2	General Ground			transition	-73.9156793	41.0424096	0.25	2019-09-23 15:22
PLS-T5	PLS-T5-3	General Ground	Cobble - Small			-73.9156432	. 41.0424440	-1.03	2019-09-23 15:23
PLS-T5	PLS-T5-4	General Ground	Cobble - Small		wsel	-73.9156170	41.0424654	-1.37	2019-09-23 15:23

TransectID	Name	PointType	DomSubstrate	WaterDepth	Comments	POINT_X	POINT_Y	ElevNAVD88, ft	GNSS Fix DateTime (GMT)
PLS-T5	PLS-T5-5	General Ground			transition	-73.9155491	41.0425150	-2.19	2019-09-23 15:24
PLS-T5	PLS-T5-6	General Ground	Silt/Clay			-73.9155237	41.0425335	-2.17	2019-09-23 15:24
PLS-T6	PLS-T6-1		Boulder - Medium			-73.9155700	41.0422862	2.46	2019-09-23 15:25
PLS-T6	PLS-T6-2	General Ground			transition	-73.9155312	41.0423267	-0.25	2019-09-23 15:26
PLS-T6	PLS-T6-3	General Ground	Cobble - Large			-73.9155137	41.0423444		
PLS-T6	PLS-T6-4	General Ground			wsel	-73.9155036	41.0423605		2019-09-23 15:26
PLS-T6	PLS-T6-5	General Ground	Ŭ		transition	-73.9154381	41.0424049		
PLS-T6	PLS-T6-6	General Ground			transition	-73.9154442	41.0424035		2019-09-23 15:32
PLS-T6	PLS-T6-7	General Ground	Silt/Clay			-73.9153908	41.0424443		2019-09-23 15:33
PLS-T7	PLS-T7-1	General Ground	Cobble - Large			-73.9154134	41.0422523		2019-09-23 15:34
PLS-T7	PLS-T7-2	General Ground	v			-73.9154131	41.0422832		2019-09-23 15:35
PLS-T7	PLS-T7-3	General Ground				-73.9154105	41.0423106		2019-09-23 15:35
PLS-T7	PLS-T7-4	General Ground			transition	-73.9154241	41.0423894		2019-09-23 15:36
PLS-T7	PLS-T7-5	General Ground	Silt/Clav			-73.9154397	41.0424345		2019-09-23 15:37
PLS-T7	PLS-T7-6	General Ground				-73.9154460	41.0424510		2019-09-23 15:37
PLS-T8	PLS-T8-1	General Ground				-73.9152321	41.0422567		2019-09-23 15:38
PLS-T8	PLS-T8-2	General Ground			transition	-73.9152332	41.0422732		
PLS-T8	PLS-T8-3	General Ground	Gravel - Coarse			-73.9152329	41.0422834		2019-09-23 15:39
PLS-T8	PLS-T8-4	General Ground				-73.9152422	41.0423579		2019-09-23 15:40
PLS-T8	PLS-T8-5	General Ground			transition	-73.9152471	41.0423817		2019-09-23 15:40
PLS-T8	PLS-T8-6	General Ground	Silt/Clay			-73.9152638	41.0424369		2019-09-23 15:44
PLS-T8	PLS-T8-7	General Ground				-73.9152639	41.0424555		2019-09-23 15:45
PLS-T8	PLS-T8-8	Other			storm water pipe	-73.9152287	41.0422540		2019-09-23 15:46
PLS-T9	PLS-T9-1	General Ground	Gravel - Coarse			-73.9150596	41.0422630		2019-09-23 17:27
PLS-T9	PLS-T9-2	General Ground				-73.9150630	41.0423147		2019-09-23 17:27
PLS-T9	PLS-T9-3	General Ground			transition	-73.9150621	41.0423256		
PLS-T9	PLS-T9-4	General Ground	Silt/Clay			-73.9150606	41.0423901		2019-09-23 17:28
PLS-T9	PLS-T9-5	General Ground				-73.9150753	41.0424409		2019-09-23 17:28
PLS-T9	PLS-T9-6	General Ground	· •			-73.9150826	41.0424748		2019-09-23 17:28
PLS-T10	PLS-T10-1	General Ground				-73.9148944	41.0424769		2019-09-23 17:24
PLS-T10	PLS-T10-2	General Ground				-73.9148914	41.0423972		2019-09-23 17:24
PLS-T10	PLS-T10-3	General Ground	Shiry Cluy		transition	-73.9148930	41.0423315		2019-09-23 17:24
PLS-T10	PLS-T10-4	General Ground	Gravel - Coarse			-73.9148751	41.0423009		2019-09-23 17:26
PLS-T10	PLS-T10-5	General Ground				-73.9148747	41.0422744		2019-09-23 17:26
PLS-T11	PLS-T11-1	General Ground				-73.9147117	41.0422651		2019-09-23 17:20
PLS-T11	PLS-T11-2	General Ground			wsel	-73.9147131	41.0422779		2019-09-23 17:20
PLS-T11	PLS-T11-3	General Ground			transition	-73.9147132	41.0422838		2019-09-23 17:20
PLS-T11	PLS-T11-5		Boulder - Medium			-73.9147132	41.0423019		2019-09-23 17:20
PLS-T11	PLS-T11-4	General Ground			transition	-73.9147073	41.0423234		2019-09-23 17:21
PLS-T11 PLS-T11	PLS-T11-5 PLS-T11-6	General Ground				-73.9147073	41.0423234		2019-09-23 17:22
PLS-T11 PLS-T11	PLS-T11-0 PLS-T11-7	General Ground				-73.9147109	41.0423717		2019-09-23 17:22
PLS-T11 PLS-T11	PLS-T11-7 PLS-T11-8	General Ground				-73.9147048	41.0424201		2019-09-23 17:22
PLS-T11 PLS-T12	PLS-T11-8 PLS-T12-1	General Ground				-73.9147004	41.0424607		2019-09-23 17:23
PLS-T12 PLS-T12	PLS-T12-1 PLS-T12-2	General Ground				-73.9145202	41.0424362		
PLS-T12 PLS-T12	PLS-T12-2 PLS-T12-3	General Ground			transition	-73.9145202	41.0423923		2019-09-23 16:40
PLS-T12	PLS-T12-4	General Ground				-73.9145194	41.0423224		2019-09-23 16:42
PLS-T12	PLS-T12-5	General Ground				-73.9145286	41.0422918		
PLS-T12	PLS-T12-6	General Ground	Graver - Coarse			-73.9145208	41.0422621	-0.56	2019-09-23 16:43

TransectID	Name	PointType	DomSubstrate	WaterDepth	Comments	POINT_X	POINT_Y	ElevNAVD88, ft	GNSS Fix DateTime (GMT)
PLS-T13	PLS-T13-1	General Ground	Gravel - Coarse			-73.9143375	41.0422448	-0.33	2019-09-23 16:36
PLS-T13	PLS-T13-2	General Ground	Gravel - Coarse		wsel	-73.9143396	41.0422609	-0.87	2019-09-23 16:37
PLS-T13	PLS-T13-3	General Ground			transition	-73.9143417	41.0423115	-2.50	2019-09-23 16:37
PLS-T13	PLS-T13-4	General Ground	Silt/Clay			-73.9143445	41.0423644	-2.81	2019-09-23 16:38
PLS-T13	PLS-T13-5	General Ground	Silt/Clay			-73.9143364	41.0424234	-3.09	2019-09-23 16:38
PLS-T13	PLS-T13-6	General Ground	Silt/Clay			-73.9143315	41.0424542	-3.20	2019-09-23 16:39
PLS-T14	PLS-T14-1	General Ground	Sand - Fine			-73.9141465	41.0424387		2019-09-23 16:31
PLS-T14	PLS-T14-2	General Ground	Sand - Fine			-73.9141587	41.0423607	-2.89	2019-09-23 16:32
PLS-T14	PLS-T14-3	General Ground			transition	-73.9141643	41.0423073	-2.19	2019-09-23 16:33
PLS-T14	PLS-T14-4	General Ground	Cobble - Small		wsel	-73.9141498	41.0422587	-0.98	2019-09-23 16:34
PLS-T14	PLS-T14-5	General Ground	Cobble - Small			-73.9141509	41.0422460	-0.53	2019-09-23 16:34
PLS-T14	PLS-T14-6	General Ground	Cobble - Small			-73.9141537	41.0422374	-0.31	2019-09-23 16:35
PLS-T15	PLS-T15-1	General Ground	Boulder - Small			-73.9137962	41.0422322	0.18	2019-09-23 16:26
PLS-T15	PLS-T15-2	General Ground			transition	-73.9137932	41.0422607		2019-09-23 16:26
PLS-T15	PLS-T15-3	General Ground	Cobble - Large			-73.9137892	41.0423198		2019-09-23 16:27
PLS-T15	PLS-T15-4	General Ground	Cobble - Large			-73.9137787	41.0424013	-2.67	2019-09-23 16:29
PLS-T15	PLS-T15-5	General Ground	5			-73.9137949	41.0424344		
PLS-T16	PLS-T16-1	General Ground				-73.9133645	41.0423573		2019-09-23 16:21
PLS-T16	PLS-T16-2	General Ground				-73.9133922	41.0422735		2019-09-23 16:22
PLS-T16	PLS-T16-3	General Ground			transition	-73.9134122	41.0422362		2019-09-23 16:23
PLS-T16	PLS-T16-4	General Ground	Cobble - Large		wsel	-73.9134328	41.0421959		2019-09-23 16:23
PLS-T16	PLS-T16-5	General Ground	, v			-73.9134484	41.0421664		2019-09-23 16:24
PLS-T17	PLS-T17-1	General Ground				-73.9130075	41.0422773		2019-09-23 14:34
PLS-T17	PLS-T17-2	General Ground				-73.9131099	41.0420872		2019-09-23 16:17
PLS-T17	PLS-T17-3	General Ground				-73.9131011	41.0420977		2019-09-23 16:17
PLS-T17	PLS-T17-4	General Ground			transition	-73.9130954	41.0421067		2019-09-23 16:18
PLS-T17	PLS-T17-5	General Ground	Cobble - Small		wsel	-73.9130885	41.0421190		2019-09-23 16:18
PLS-T17	PLS-T17-6	General Ground			transition	-73.9130744	41.0421583		2019-09-23 16:19
PLS-T17	PLS-T17-7	General Ground	Silt/Clav			-73.9130416	41.0422008		2019-09-23 16:19
PLS-T17	PLS-T17-8	General Ground				-73.9130237	41.0422716		2019-09-23 16:20
-	GCP-1	Other			GCP-1	-73.9154096	41.0415186		2019-09-23 13:23
	GCP-2	Other			GCP-2	-73.9145427	41.0415413		2019-09-23 13:25
	GCP-3	Other			GCP-3	-73.9145439	41.0421844		2019-09-23 13:29
	GCP-4	Other			GCP-4	-73.9160255	41.0425887		2019-09-23 13:32
	PLS-GS-1	General Ground			parking lot curb	-73.9166031	41.0419033		2019-09-23 13:54
	PLS-GS-2	General Ground			parking lot curb	-73.9166186	41.0421664		2019-09-23 13:55
	PLS-GS-3	General Ground			catch basin	-73.9164266	41.0421870		2019-09-23 13:56
	PLS-GS-4	General Ground			catch basin	-73.9164147	41.0423015		2019-09-23 13:57
	PLS-GS-5	General Ground			catch basin	-73.9164106	41.0423810		2019-09-23 13:57
	PLS-GS-6	General Ground			gate to community garden	-73.9164318	41.0425435		
	PLS-GS-7	General Ground			center of community garden	-73.9165363	41.0425173		2019-09-23 14:01
	PLS-GS-8		Vegetation - Herbaceou	s		-73.9163005	41.0425973		
	PLS-GS-9		Vegetation - Herbaceou		overlook decking	-73.9162421	41.0427130		
	PLS-GS-10		Vegetation - Herbaceou		overlook decking	-73.9161459	41.0426389		2019-09-23 14:00
	PLS-GS-11		Vegetation - Herbaceou			-73.9161428	41.0425183		2019-09-23 14:07
	PLS-GS-11 PLS-GS-12	Other		-	ground at tree, ornamental beech	-73.9160712	41.0424705		2019-09-23 14:07
	PLS-GS-12 PLS-GS-13	Other			ground at tree, red maple, 16"	-73.9162691	41.0424532		
	PLS-GS-13 PLS-GS-14	Other			ground at tree, crab apple	-73.9163707	41.0424332		

TransectID Name	PointType	DomSubstrate	WaterDepth	Comments	POINT_X	POINT_Y	ElevNAVD88, ft	GNSS Fix DateTime (GMT)
PLS-GS-15	Other			ground at tree, crab apple	-73.9164119	41.0425756	3.98	2019-09-23 14:14
PLS-GS-16	General Ground			curb	-73.9161771	41.0423578	3.39	2019-09-23 14:16
PLS-GS-17	General Ground			catch basin	-73.9160936	41.0422423	1.98	2019-09-23 14:16
PLS-GS-18	General Ground			catch basin	-73.9160740	41.0420654	2.18	2019-09-23 14:17
PLS-GS-19	General Ground			curb	-73.9160349	41.0418918	3.39	2019-09-23 14:17
PLS-GS-20	General Ground			catch basin	-73.9158857	41.0419223	3.09	2019-09-23 14:19
PLS-GS-21	General Ground			lot corner curb	-73.9157576	41.0419098	4.87	2019-09-23 14:19
PLS-GS-22	General Ground			curb	-73.9157918	41.0420285	4.56	2019-09-23 14:20
PLS-GS-23	General Ground	Gravel - Medium			-73.9158134	41.0421604	3.73	2019-09-23 14:20
PLS-GS-24	General Ground			top wall	-73.9157777	41.0421654	6.89	2019-09-23 14:21
PLS-GS-25	General Ground			top wall	-73.9157656	41.0420636	6.76	2019-09-23 14:21
PLS-GS-26	General Ground			top end wall	-73.9158627	41.0422820	6.94	2019-09-23 14:22
PLS-GS-27	General Ground			top corner wall	-73.9157919	41.0422861	6.98	2019-09-23 14:22
PLS-GS-28	General Ground			top end wall	-73.9157662	41.0420638	6.79	2019-09-23 14:24
PLS-GS-29	Other			tree, mulberry	-73.9158476	41.0423384	8.71	2019-09-23 14:25
PLS-GS-30	General Ground			paved walkway	-73.9158261	41.0423951	6.66	2019-09-23 14:27
PLS-GS-31	General Ground			top wall	-73.9158257	41.0423979	8.17	2019-09-23 14:27
PLS-GS-32	General Ground	Boulder - Medium	0		-73.9138034	41.0427628	-1.14	2019-09-23 14:28
PLS-GS-33	General Ground			top wall at gate	-73.9157112	41.0423291	8.41	2019-09-23 14:28
PLS-GS-34	General Ground				-73.9156203	41.0421539	6.35	2019-09-23 14:29
PLS-GS-35	General Ground			catch basin	-73.9155797	41.0420862	6.73	2019-09-23 14:30
PLS-GS-36		Boulder - Medium	0		-73.9137915	41.0426118		
PLS-GS-37	General Ground			catch basin	-73.9156368	41.0420366		2019-09-23 14:30
PLS-GS-38	General Ground			top curb	-73.9156285	41.0420402		2019-09-23 14:31
PLS-GS-39	General Ground			corner curb	-73.9155772	41.0419555		2019-09-23 14:31
PLS-GS-40	General Ground			catch basin	-73.9155868	41.0419222		2019-09-23 14:31
PLS-GS-41	General Ground			catch basin	-73.9156660	41.0419164	6.41	2019-09-23 14:32
PLS-GS-42	General Ground			top curb	-73.9155599	41.0417262	7.48	2019-09-23 14:32
PLS-GS-43		Vegetation - Herbaceous		•	-73.9153618	41.0417327		
PLS-GS-44		Vegetation - Herbaceous			-73.9151800	41.0415637	8.00	
PLS-GS-45	General Ground			top curb	-73.9152161	41.0414648	7.63	2019-09-23 14:34
PLS-GS-46	General Ground			flag pole	-73.9150502	41.0417432		2019-09-23 14:35
PLS-GS-47	General Ground			top curb	-73.9150821	41.0420084		2019-09-23 14:35
PLS-GS-48	General Ground			top curb	-73.9150920	41.0420745	8.09	2019-09-23 14:36
PLS-GS-49	General Ground	Silt/Clay		· ·	-73.9130328	41.0425773	-3.91	2019-09-23 14:36
PLS-GS-50	General Ground			south center of gazebo	-73.9151004	41.0421755	7.87	2019-09-23 14:36
PLS-GS-51	General Ground			north center of gazebo	-73.9151053	41.0422289		2019-09-23 14:37
PLS-GS-52	General Ground			top wall	-73.9151084	41.0422424		2019-09-23 14:37
PLS-GS-53		Sand - Very Fine			-73.9134676	41.0429866		2019-09-23 14:37
PLS-GS-54	General Ground			top outer wall	-73.9151139	41.0422539		
PLS-GS-55	General Ground			ground wall	-73.9151118	41.0422452		
PLS-GS-56	General Ground		1	paved ground wall	-73.9151102	41.0422422		
PLS-GS-57		Sand - Very Fine	1		-73.9141927	41.0432655		
PLS-GS-58	General Ground		1	maintenance point access to storm drain	-73.9152323	41.0421822		
PLS-GS-59	General Ground				-73.9150350	41.0432844		2019-09-23 14:41
PLS-GS-60	General Ground			top outer wall	-73.9154363	41.0422325		
PLS-GS-61	General Ground			ground at wall	-73.9154337	41.0422243		
PLS-GS-62	General Ground			top wall	-73.9154339	41.04222243		

TransectID Name	PointType	DomSubstrate WaterDepth	Comments	POINT_X	POINT_Y	ElevNAVD88, ft	GNSS Fix DateTime (GMT)
PLS-GS-63	General Ground		pavement at wall	-73.9154340	41.0422207	7.29	2019-09-23 14:42
PLS-GS-64	General Ground		top wall	-73.9155242	41.0422150	8.56	2019-09-23 14:43
PLS-GS-65	General Ground		pavement at wall	-73.9155238	41.0422142	7.35	2019-09-23 14:43
PLS-GS-66	General Ground		top wall	-73.9148666	41.0422578	8.47	2019-09-23 14:44
PLS-GS-67	General Ground		ground at wall	-73.9148675	41.0422609	6.62	2019-09-23 14:44
PLS-GS-68	General Ground		top outer wall	-73.9148662	41.0422680	7.23	2019-09-23 14:44
PLS-GS-69	General Ground		pavement at wall	-73.9148684	41.0422569	7.33	2019-09-23 14:45
PLS-GS-70	General Ground		pavement at wall	-73.9148356	41.0422401	7.48	2019-09-23 14:46
PLS-GS-71	General Ground		top wall	-73.9148360	41.0422406	8.56	2019-09-23 14:46
PLS-GS-72	General Ground		top curb	-73.9148422	41.0420909	7.55	2019-09-23 14:48
PLS-GS-73	General Ground		top curb	-73.9148321	41.0420238	7.41	2019-09-23 14:48
PLS-GS-74	General Ground		center walkway	-73.9148247	41.0418824	8.32	2019-09-23 14:48
PLS-GS-75	General Ground	Vegetation - Herbaceous		-73.9147499	41.0417858	8.57	2019-09-23 14:49
PLS-GS-76	General Ground		sidewalk	-73.9147352	41.0416024		
PLS-GS-77	General Ground		top curb	-73.9146918	41.0414988	8.33	2019-09-23 14:50
PLS-GS-78	General Ground		corner of flywheel monument	-73.9146624	41.0415430		
PLS-GS-79	General Ground		corner of flywheel monument	-73.9145479	41.0415527	8.45	2019-09-23 14:53
PLS-GS-80	General Ground		corner of flywheel monument	-73.9145576	41.0416502	8.28	
PLS-GS-81	General Ground		corner of flywheel monument	-73.9146737	41.0416419	8.72	2019-09-23 14:52
PLS-GS-82	General Ground		top curb	-73.9145457	41.0417599	8.01	2019-09-23 14:53
PLS-GS-83	General Ground		catch basin	-73.9146604	41.0420376	6.50	2019-09-23 14:54
PLS-GS-84	General Ground		top curb	-73.9146155	41.0420359		
PLS-GS-85	General Ground		catch basin	-73.9146653	41.0420997		
PLS-GS-86	General Ground		top curb	-73.9145709	41.0420959		
PLS-GS-87	General Ground		sewer manhole cover	-73.9145109	41.0421119	7.68	
PLS-GS-88		Vegetation - Herbaceous		-73.9145801	41.0421767		
PLS-GS-89	General Ground		manhole cover	-73.9145301	41.0422192		
PLS-GS-90	General Ground		hydrant	-73.9144625	41.0420905	7.89	2019-09-23 14:57
PLS-GS-91	General Ground		sidewalk	-73.9143932	41.0421487		
PLS-GS-92	General Ground		sidewalk in front of gate to the View	-73.9141735	41.0422124	7.61	2019-09-23 14:58
PLS-GS-93	General Ground	Boulder - Small	top outer wall, transition point to boulder wall	-73.9148322	41.0422523	6.92	2019-09-23 15:02
PLS-GS-94	General Ground		top wall	-73.9137406	41.0422072	8.68	2019-09-23 15:04
PLS-GS-95	General Ground		ground at wall	-73.9137410	41.0422057		
PLS-GS-96	General Ground		ground at wall	-73.9137388	41.0422093		
PLS-GS-97	General Ground		top outer wall, concrete on top of small boulders	-73.9137361	41.0422184		
PLS-GS-98	General Ground	Sand - Medium		-73.9161475	41.0426590	3.76	2019-09-23 15:00
PLS-GS-99	General Ground		pavement at wall	-73.9131210	41.0420611	7.95	2019-09-23 15:06
PLS-GS-10) General Ground		top wall	-73.9131214	41.0420639	8.74	2019-09-23 15:07
PLS-GS-10	General Ground		ground at wall	-73.9131223	41.0420645	8.20	2019-09-23 15:09
	2 General Ground	Boulder - Small	top outer wall, rip rap	-73.9131208	41.0420741		
PLS-GS-103			catch basin	-73.9131347	41.0419974		
PLS-GS-104			hydrant	-73.9131247	41.0419820		
PLS-GS-10			top curb	-73.9130674	41.0420182		
PLS-GS-10			water main access, V91 marker	-73.9131024	41.0420368		
PLS-GS-10			water main access, V92 marker	-73.9131432	41.0420304		
PLS-GS-108			water main access	-73.9131507	41.0419869		
PLS-GS-10			top curb	-73.9132400	41.0420677		
PLS-GS-110			catch basin	-73.9132440	41.0420529		

TransectID Name	PointType	DomSubstrate	WaterDepth	Comments	POINT_X	POINT_Y	ElevNAVD88, ft	GNSS Fix DateTime (GMT)
PLS-GS-111	Photo				-73.9132031	41.0420522	9.29	2019-09-23 15:16
PLS-GS-112	Photo				-73.9138596	41.0422088	7.51	2019-09-23 15:17
PLS-GS-113	Photo				-73.9142740	41.0422127	8.88	2019-09-23 15:18
PLS-GS-114	Photo				-73.9146827	41.0419954	9.16	2019-09-23 15:19
PLS-GS-115	Photo				-73.9153466	41.0422148	7.62	2019-09-23 15:21
PLS-GS-116	Photo				-73.9156899	41.0419422	8.39	2019-09-23 15:23
PLS-GS-117	General Ground			east corner of overlook decking	-73.9158960	41.0424633	5.59	2019-09-23 15:34
PLS-GS-118	General Ground			southeast corner of overlook decking	-73.9159129	41.0424507	5.51	2019-09-23 15:34
PLS-GS-119	General Ground			edge of overlook decking at stairs	-73.9160715	41.0425963	5.60	2019-09-23 15:35
PLS-GS-120	General Ground			south edge of overlook decking at stairs	-73.9160868	41.0425827	5.54	2019-09-23 15:36
PLS-GS-121	General Ground			northwest corner of overlook decking	-73.9162319	41.0427161	5.43	2019-09-23 15:37
PLS-GS-122	General Ground			west corner of overlook decking	-73.9162524	41.0427071	5.38	2019-09-23 15:37
PLS-GS-123	General Ground			wooden ramp northeast corner	-73.9157594	41.0424274	2.23	2019-09-23 15:42
PLS-GS-124	General Ground			wooden ramp northwest corner	-73.9157803	41.0424169	2.34	2019-09-23 15:43
PLS-GS-125	General Ground			wooden ramp southwest corner at gate	-73.9156958	41.0423235	7.81	2019-09-23 15:43
PLS-GS-126	General Ground			wooden ramp northeast corner at gate	-73.9156762	41.0423425	7.89	2019-09-23 15:44
PLS-GS-127	General Ground			wooden ramp corner at gate	-73.9156982	41.0423547	7.75	
PLS-GS-128				wooden ramp corner at gate	-73.9157149	41.0423375	7.75	
PLS-GS-129				top end wall	-73.9158681	41.0424237	7.86	
PLS-GS-130				ground end wall	-73.9158677	41.0424226	5.99	
PLS-GS-131				ground at edge stairs	-73.9160558	41.0425985		
PLS-GS-132				ground at edge stairs	-73.9160701	41.0426092		
PLS-GS-133				top bulkhead	-73.9163088	41.0429645		
PLS-GS-134				ground at bulkhead	-73.9163056	41.0429668		2019-09-23 15:51
PLS-GS-135		Gravel - Medium		0	-73.9162662	41.0429793	-1.26	
PLS-GS-136				top cribbing	-73.9162099	41.0428208		
PLS-GS-137				ground at cribbing wall	-73.9162083	41.0428214	1.48	
PLS-GS-138		Gravel - Medium		0	-73.9161719	41.0428327	-0.03	
PLS-GS-139		Gravel - Medium			-73.9161468	41.0428470		2019-09-23 15:59
PLS-GS-140		Sand - Medium		corner if crib wall	-73.9161412	41.0427421	1.46	
PLS-GS-141		Sand - Medium		top corner if crib wall	-73.9161430	41.0427409		
PLS-GS-142				base of cell tower	-73.9158779	41.0424406		2019-09-23 16:02
PLS-GS-143					-73.9160259	41.0425886		2019-09-23 16:10
PLS-GS-144					-73.9158956	41.0424792		2019-09-23 16:18
PLS-GS-145	Other	(blank)	(blank)	pipe	-73.9151400	41.0422570		
PLS-GS-146		(blank)	(blank)	(blank)	-73.9145300	41.0422600		
PLS-GS-147		(blank)	(blank)	pipe	-73.9137610	41.0422360		
PLS-REF-P1		Gravel - Very Fine	(biank)	pipe	-73.9048137	41.0419057	0.38	
PLS-REF-P2				organic mat	-73.9048175	41.0419031	0.94	2019-09-23 17:11
PLS-REF-P3		other		wrack line	-73.9048181	41.0419797		
	1 General Ground			s. alt low elev, muck on rip rap	-73.9042939	41.0421400		
	2 General Ground			s. alterniflora low end, muck on rip rap	-73.9042939	41.0421400		
	-3 General Ground			s. alterniflora high, muck on rip rap	-73.9042524	41.0421371		
PLS-REF-T1 PLS-REF-T1			1.1	organics/muck	-73.9042524	41.0421455		
			0.7	5	-73.9042789			
PLS-REF-T1 PLS-REF-T1 PLS-REF-T1 PLS-REF-T1				organics/muck		41.0420513		
PLS-REF-T1 PLS-REF-T1 PLS-REF-T1 PLS-REF-T1			edge water	organics/muck	-73.9043563 -73.9043658	41.0421159		
PLD-KEE-II PLD-KEE-II	4 Jueneral Ground	Sand - Coarse		some riprap, gravel	-73.9043658	41.0421208	-0.28	2019-09-23 16:45

TransectID	Name	PointType	DomSubstrate	WaterDepth	Comments	POINT_X	POINT_Y	ElevNAVD88, ft	GNSS Fix DateTime (GMT)
PLS-REF-T1	PLS-REF-T1-6	General Ground	Other		s. alterniflora upper, muck on rip rap	-73.9043780	41.0421451	1.37	2019-09-23 16:47
PLS-REF-T1	PLS-REF-T1-7	General Ground	Other		s. alt end, start rip rap, muck on riprap	-73.9043803	41.0421452	1.46	2019-09-23 16:50
PLS-REF-T1	PLS-REF-T1-8	General Ground	Cobble - Large		stop rip rap, start phrag.	-73.9043796	41.0421593	2.86	2019-09-23 16:51
PLS-REF-T1	PLS-REF-T1-9	General Ground	Gravel - Medium		mug wort, road edge	-73.9043943	41.0421765	4.81	2019-09-23 17:18
PLS-REF-T2	PLS-REF-T2-1	General Ground	Other	1.0	muck	-73.9045807	41.0419343	-1.57	2019-09-23 17:09
PLS-REF-T2	PLS-REF-T2-2	General Ground	Other	1.0	muck	-73.9045932	41.0419494	-1.37	2019-09-23 17:08
PLS-REF-T2	PLS-REF-T2-3	General Ground	Other	0.90	muck	-73.9046091	41.0419671	-1.37	2019-09-23 17:08
PLS-REF-T2	PLS-REF-T2-4	General Ground	Other	0.65	muck	-73.9046220	41.0419805	-1.06	2019-09-23 17:07
PLS-REF-T2	PLS-REF-T2-5	General Ground	Sand - Medium	edge water	muck	-73.9046385	41.0419915	-0.39	2019-09-23 17:06
PLS-REF-T2	PLS-REF-T2-6	General Ground	Sand - Medium		start organic deposit	-73.9046589	41.0420146	0.93	2019-09-23 17:05
PLS-REF-T2	PLS-REF-T2-7	General Ground	Sand - Fine		edge phrag	-73.9046729	41.0420281	1.84	2019-09-23 17:05

Appendix B

Stakeholder Kickoff Meeting (August 22, 2019)

Preliminary Design Report Version - Final





Climate Adaptive Design (CAD) Studio Piermont Living Shoreline Project

Kickoff Meeting Piermont Village Hall August 22, 2019











© 2015 HDR, all rights reserved.

Agenda

- Introduce HDR team & Project Partners (Roles & Responsibilities)
- Project Background & Shared Vision
- CAD Concepts & Overall Design Objectives (Expected Outputs & Outcomes)
- QAPP & Site Investigation
- Stakeholder Engagement & Coordination
- Overall Permitting Strategy
- Project Schedule
- Site Visit





Ehren Deppert

Marc Korpus

Roles & Responsibilities

Organization	Name	Role	Responsibility
HDR	Julie Stein	HDR Principle in Charge (PiC)	Overall contract management for HDR
HDR	David S. Davis	Project Manager	 Establish and maintain project schedule and budget Stakeholder strategy and engagement Oversight and final review of all project deliverables QAPP implementation
HDR	David J. Yozzo	Senior Technical Advisor/QA	 Technical oversight of data collections and review of deliverables QAPP implementation
HDR	Barbara Barnes	Registered Landscape Architect/QC	QC Review and oversight of landscape design and deliverables
HDR	Kim Lukas	Water Resource Engineer	Review CAD conceptsPrepare engineering design report
HDR	Kevin VerWeire	Site Assessment Lead	Site assessment lead and living shoreline design
NYSDEC	Daniel Miller	NEIWPCC Project Manager	 Review and oversight of technical work progress and deliverables Coordinate NYSDEC and HREP stakeholder engagement
NEIWPCC	Peter Zaykoski	Quality Assurance Program Manager	 Contract management Review QAPP and subsequent revisions for conformance to NEIWPCC guidelines
NYSDEC/ Cornell Cooperative Extension	Libby Zemaitis	HREP Climate Outreach Specialist	Project implementation and reviews
Village of Piermont	Nathan Mitchell	Piermont Waterfront Resiliency Commission Chair	Project implementation and oversightLocal stakeholder engagement

Project Background

- Piermont's location is a great asset and offers a unique opportunity for coastal resiliency planning.
- The challenges of climate change and sea level rise will be significant:
 - ✓ 0.75 to 2.5 feet rise by 2050 and 1.25 to 9.5 feet by 2100 in lower HR estuary (NYSDEC)
 - ✓ 52.5% of Piermont at risk from 1% flood event (Rockland County Hazard Mitigation Plan)
- Through collective planning, engaged citizens and a shared stakeholder vision, Piermont is uniquely positioned to face the challenge.



From Piermont Waterfront Resiliency Commission 2018




Flooding along Paradise Avenue (Photo by DEC)

From Piermont Marsh Reserve Management Plan 2017 (NYSDEC)

Shared Vision for a Resilient Piermont


- Report of the Piermont Waterfront Resilience Task Force (2014)
- Desired outcomes from the community, a resilient Piermont will...
 - ✓ adapt gradually to avoid and minimize risks
 - ✓ be a model for others
 - help its residents and businesses to recover quickly from floods and storms
 - ✓ maintain the Village's relationship with the Hudson River
 - maintain a vibrant business district and local economy
 - ✓ foster and build community
 - ✓ be environmentally responsible






Climate Adaptive Design (CAD) Studio

- Cornell University's CAD Studio began design process in Fall 2017.
- Students developed 5 independent designs that envisioned future waterfront reinforcement, adaptation and relocation in Piermont.
- Each of the CAD Studio designs offers well thought out, innovative ideas for improving Piermont's coastal resiliency.



Design Objective

- Review CAD Studio concepts and use common elements to develop a cohesive and implementable design for a coastal resiliency project.
- Must achieve five overarching criteria:
 - Be cost-effective and able to attain state and local agency support and permits
 - Align with Piermont's existing Waterfront Resiliency Program and Local Waterfront Revitalization Plan (LWRP)
 - Align with the goals of the Hudson River Estuary Program and nearby Piermont Marsh reserve.
 - Be in keeping with the village's scenic and waterfront character
 - ✓ Include educational or interpretive elements



Site Identification


- During the RFP stage, HDR met with the Village and identified a potential project area north of the existing pier.
- Public open space area that could offer an opportunity to restore ecological diversity and protect a mix of land uses and infrastructure offset from the waterfront.
- An ecological and general site condition assessment will be conducted during a one-day site investigation planned for mid to late September.



FJ


Design Methodology

- Preliminary design will follow the guidance outlined by NYSDEC for Marine and Coastal District Waters including the Hudson River south of the Tappan Zee Bridge.
- Living shorelines use vegetation and other natural elements, such as oysters or mussel beds, often in combination with harder shoreline structures to stabilize and protect coastlines in an estuarine system.
- Added benefits:
 - Improving water quality by filtering nutrients and pollutants,
 - Creating habitat for fish, birds and other living resources,
 - ✓ Promoting recreation and adaptive uses.



Preliminary Design (to be investigated)

- Incorporate additional structured protection as appropriate to stabilize the slope and protect against erosive forces such as boat wakes, ice scour and storm surge.
- Low profile sills made of broken rock, bagged mixed mollusk shells, modular oyster "castles", or concrete reef balls to protect marsh plantings and provide additional habitat for aquatic organisms.



First Steps

- ✓ Finalize Quality Assurance Project Plan (QAPP)
- ✓ Project Kickoff Meeting (August 22, 2019)
- Review CAD Concepts and Develop Checklist of Key Elements
- Conduct Site Assessment (September 2019)



Northern pier ecological buffer and podestrian walkway to protect Pierment against wave action and reduce sediment deposition

Site Assessment (Topo)

- Review existing data (see NOAA Digital Coast Topobathymetry Base Map with elevation contours).
- Aerial drone survey will collect aerial imagery, videography, and photogrammetry as well as highaccuracy topography.
- Water elevations collected at low tide every 50 feet along the shoreline as well as locations of both natural and man-made features to a wadeable depth using RTK GPS.



Site Assessment (Ecological and General Site Condition)

- Describe existing ecological communities based on Edinger *et al.* 2014
- Record:
 - ✓ Dominant plant species
 - ✓ Invasive species present
 - ✓ Rare plants or animals observed
 - ✓ Dominant substrate types
 - Visual assessment of bank and shoreline stability
 - Observed site constraints and ecological opportunities



Stakeholder Engagement

- Stakeholder engagement will guide the selection of design features and refine preliminary concept design.
- Key stakeholders include:
 - ✓ NYSDEC Hudson River Estuary Program (HREP)
 - ✓ NYSDEC Division of Fish & Wildlife (Regulatory)
 - ✓ Hudson River National Estuarine Research Reserve (HRNERR)
 - ✓ Hudson River Sustainable Shorelines Project
 - New England Interstate Water Pollution Control Commission (NEIWPCC)
 - ✓ U.S. Army Corps of Engineers New York District
 - ✓ NOAA National Marine Fisheries Service (NMFS)
 - ✓ Village of Piermont
 - ✓ Piermont Waterfront Resiliency Commission
 - ✓ Cornell University
 - ✓ Scenic Hudson





Local Stakeholders

- Village staff will assist planning and stakeholder engagement including coordination with property/landowners at the community level.
- Concurrent Projects Near Parelli Park:
 - Rebuild of Public Boat Ramp Damaged during Superstorm Sandy
 - ✓ Memorial Lighthouse Project





Permitting Strategy

- As part of the Preliminary Design Report, HDR will outline an overall permitting strategy for the proposed project.
- HDR will prepare materials and attend a pre-application meeting with relevant state and federal regulatory staff to review the draft preliminary design.
- No permit applications will be filed under this contract.



Preliminary Concept Design Deliverables

- Engineering Report and Drawings (Draft & Final)
- Summary of CAD Studio Design Review and Project Justification
- Stakeholder Engagement Summary
- Site Assessment Summary
- Permitting Strategy and Compiled Application Materials
- Implementation Strategy that estimates:
 - Future construction and maintenance costs
 - Permitting and construction timelines
 - Recommended project specifications with construction, maintenance and monitoring considerations
 - ✓ Potential funding source(s)
 - General implementation recommendations



Project Schedule with Key Milestones & Deliverables

MONTH	JUL	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SE
MILESTONES												-			
Notice of Funding Award 🛛 😽 🕅	ay 201	9			1	8	î — î				i di			1	0
Project Start Date											1				
Final QAPP															
Kick-off Meeting		0													
Site Assessment			•												
Draft Preliminary Design with Progress Report		l l					1 1	•	100					(
Intermediate Stakeholder Meeting								081901	0					Į	
Draft Final Preliminary Design												•			
Pre-Application Meeting	1												0		
Final Stakeholder Meeting														0	
Final Report & Deliverables to NEIWPCC	1						i T								*
Quarterly Reporting			•		_	•			٠		ļ	•			
PROFESSIONAL SERVICES															
Task A Prepare QAPP							0								
Task B Stakeholder Strategey and Meetings				(e	14 - M								
Task C Review Existing CAD Concepts		t i				j.	t t			1					
Task D Site Assessment		. 1													
Task E Coordinate with NYSDEC			- A			<u> </u>					-				
Task F Stakeholder Engagement	Î.														
Task G Pre-Application Meeting													0		
Task H Draft Preliminary Design							8 1			_					1
Task I Final Preliminary Design & Reviews	1),				1				J.		0		

Discussion

- Questions for the project team?
- Action Items
- HDR will prepare a meeting summary for review and inclusion in the Preliminary Design Report
- Site Visit



Appendix C

NYSDEC Pre-application Meeting (June 26, 2020)

> Preliminary Design Report Version - Final



Climate Adaptive Design (CAD) Studio Piermont (Hudson River) Living Shoreline Preliminary Design Project NYSDEC Pre-Application Meeting

June 26, 2020









© 2015 HDR, all rights reserved.

Meeting Agenda

- Introductions
- Overview of the Cornell Climate Adaptive Design (CAD) Studio program
- Design goals for the Piermont Living Shoreline
- Review the project's preliminary/30% design plans
- Permitting discussion
- Next steps/Action Items



Project Background

- Piermont's location is a great asset and offers a unique opportunity for coastal resiliency planning.
- The challenges of climate change and sea level rise will be significant:
 - ✓ 0.75 to 2.5 feet rise by 2050 and 1.25 to 9.5 feet by 2100 in lower HR estuary (NYSDEC)
 - ✓ 52.5% of Piermont at risk from 1% flood event (Rockland County Hazard Mitigation Plan)
- Through collective planning, engaged citizens and a shared stakeholder vision, Piermont is uniquely positioned to face the challenge.



From Piermont Waterfront Resiliency Commission 2018




Flooding along Paradise Avenue (Photo by DEC)

From Piermont Marsh Reserve Management Plan 2017 (NYSDEC)

Shared Vision for a Resilient Piermont


- Report of the Piermont Waterfront Resilience Task Force (2014)
- Desired outcomes from the community, a resilient Piermont will...
 - ✓ adapt gradually to avoid and minimize risks
 - ✓ be a model for others
 - help its residents and businesses to recover quickly from floods and storms
 - ✓ maintain the Village's relationship with the Hudson River
 - maintain a vibrant business district and local economy
 - ✓ foster and build community
 - ✓ be environmentally responsible






Climate Adaptive Design (CAD) Studio

- Cornell University's CAD Studio began design process in Fall 2017.
- Students developed 5 independent designs that envisioned future waterfront reinforcement, adaptation and relocation in Piermont.
- Each of the CAD Studio designs offers well thought out, innovative ideas for improving Piermont's coastal resiliency.



Design Objective

- Review CAD Studio concepts and use common elements to develop a cohesive and implementable design for a coastal resiliency project.
- Must achieve five overarching criteria:
 - Be cost-effective and able to attain state and local agency support and permits
 - Align with Piermont's existing Waterfront Resiliency Program and Local Waterfront Revitalization Plan (LWRP)
 - Align with the goals of the Hudson River Estuary Program and nearby Piermont Marsh reserve.
 - Be in keeping with the village's scenic and waterfront character
 - ✓ Include educational or interpretive elements



Site Identification


- During the RFP stage, HDR met with the Village and identified a potential project area north of the existing pier.
- Public open space area that could offer an opportunity to restore ecological diversity and protect a mix of land uses and infrastructure offset from the waterfront.
- An ecological and general site condition assessment was conducted in September 2019.



FJ

Site Assessment (Topo)

- Review existing data (see NOAA Digital Coast Topobathymetry Base Map with elevation contours).
- Aerial drone survey will collect aerial imagery, videography, and photogrammetry as well as highaccuracy topography.
- Water elevations collected at low tide every 50 feet along the shoreline as well as locations of both natural and man-made features to a wadeable depth using RTK GPS.






Site Assessment (Ecological and General Site Condition)

- Describe existing ecological communities based on Edinger *et al.* 2014
- Record:
 - ✓ Dominant plant species
 - ✓ Invasive species present
 - Rare plants or animals observed
 - ✓ Dominant substrate types
 - Visual assessment of bank and shoreline stability
 - Observed site constraints and ecological opportunities



Design Methodology

- Preliminary design follows the guidance outlined by NYSDEC for Marine and Coastal District Waters including the Hudson River south of the Tappan Zee Bridge.
- Improve coastal resiliency by protecting and stabilizing the existing shoreline through the development of both intertidal and subtidal habitat features to attenuate wave energy.
- Added benefits:
 - Improving water quality by filtering nutrients and pollutants,
 - Creating habitat for fish, birds and other living resources,
 - ✓ Promoting recreation and adaptive uses.



Preliminary Design - Proposed Site Plan

DRAFT FINAL FOR PERMITTING REVIEW PRELIMINARY DRAFT FOR CLIENT REVIEW

DESCRIPTION

PROJECT NUMBER 00000010177418

05.15.20 02-14-20


DATE




CLIMATE ADAPTIVE DESIGN (CAD) STUDIO PIERMONT LIVING SHORELINE PROJECT PIERMONT, NEW YORK

EU ENAME C-101 SCALE 11 = 30

Preliminary Design – Cross Section



Preliminary Design – Rock Jetty Cross Section



Permitting Discussion

- Early engagement of regulatory staff.
- Document the type of project information required by regulatory staff for future permit approvals.
- Opportunity to provide initial feedback and perspective to be used in future design development.
- Actual permit applications will be submitted during the next phase of the project.

Habitat Zone	Habitat Area (Acre)	Habitat Area (ft^²)	Estimated Fill Depth (ft)	Estimated Fill Volume (CY)
Rock Jetty	0.20	8,787	5	1,925
Rock Low Sill	0.19	8,145	4	1,207
Low Marsh	0.19	8,264	4	1,224
High Marsh	0.23	10,054	5	1,862
Pocket Sand Beach (microhabitat areas)	0.01	605	1	11
Sand/Low Density Boulder Terrace	0.26	11,329	4	1,678
Sand/Gravel/Boat Launch Path	0.02	934	1	35
Sand Beach	0.10	4,285	1	159
Pathway Rock	0.00	154	1	6
Reef Balls	0.03	1,225	1	45
Totals	1.23	53,782		8,151

Project would result in the creation and enhancement of 1.23 acres of intertidal and subtidal habitat.

Next Steps/Action Items



Appendix D

Reasonable Order of Magnitude - Opinion of Probable Final Design and Construction Costs

Item No. Task Quantity UOM Unit Cost (2020\$) Total Cost (2020\$) Assumptions & Notes Soft Costs I Delineation of Wetlands and Waters/Functional Assessment 1 EA \$ 10,000 Includes Phase 1A/B archeological sur and coordination with SHPO. 3 Threatened and Endangered Species Consultation 1 EA \$ 10,000 Includes Phase 1A/B archeological sur and coordination with SHPO. 3 Threatened and Endangered Species Consultation 1 EA \$ 5,000 \$ 10,000 Includes Phase 1A/B archeological sur and coordination with SHPO. 4 Phase 1 Environmental Site Assessment 1 EA \$ 10,000 \$ 10,000 S ediment sampling to confirm materia classification and required management during construction and genetech sampling S ediment / Geotechnical Sampling 1 EA \$ 40,000 \$ 40,000 S ediment sampling to confirm materia classification and required management during construction and genetech sampling 6 Its survey (property lines, utilities, topography) 1 EA \$ 15,000 For approx. 1 acre site 7 65% Design Plans 6 EA \$ 15,000 \$ 90,000 5% Design	Piermont Climate		e Design of Magnitude - Opinion of Probable Construction Costs - May	2020				
infer form: infer August 1			, °, °, °, °,	1	цом	Unit Cost (2020\$s)	Total Cost (2020\$s)	Assumptions & Notes
For the second of the secon		nem no.	TUSK	Quantity	COM	0111 0031 (202033)	10101 0030 (202033)	
2 secon 10 1 1 5 1,000 5 1,000 Mode Service of Contraction of Con	50,1 00515	1	Delineation of Wetlands and Waters/Functional Assessment	1	EA	\$ 10.000	\$ 10.000	Delineation for approx, 1 acre acre site
Image: set in the set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation Image: set is and integrated species Consultation<		-			F A			Includes Phase 1A/B archeological survey
3 Provesting is a second constraint of a second con		2	Section 106	1	EA	\$ 10,000	\$ 10,000	and coordination with SHPO.
ith Aussent ith Aussent i		,	Threatened and Endangered Species Consultation	1	EA	¢ 5.000	¢ 5.000	Basic habitat assessment, coordination
Immediation S Section of Control Contro Control Control Control Contro Control Contro Control		3	Theatened and Endangered Species Consultation	1	EA	\$ 5,000	\$ 5,000	with USFWS and NY
Provide		4	Phase 1 Environmental Site Assessment	1	EA	\$ 10,000	\$ 10,000	
 s sutment / Genet-church Sampling s settimet / Genet-church Sampling s settimet / Genet-church Sampling s statimet / Genet	/ Investigation							Sediment sampling to confirm material
Vertex Subserved S		5	Sediment / Geotechnical Sampling	1	EA	\$ 40,000	\$ 40,000	classification and required management during construction and geotech samples for evaluating stability of existing jetty
2 565 Rouge Prime 6 6 A 8 15.000 9 9000 950 Rouge Prime 9 Field Contract Drawings - 1000 Regime 6 6 A 5 7.000 5 4.000 950 Rouge Prime 9 Field Contract Drawings - 1000 Regime 6 6 A 5 7.000 5 4.000 950 Rouge Prime 11 Contraction Brain Prime 12 6 A 5 5.000 5 0.000 9000 Rest Prime 12 Contraction Brain Prime 12 6 A 5 5.000 5 0.000 Rest Prime 1000 Rest Prime 13 U.S. Army Corps of Engineers Permitting 1 EA 5 50000 5 50000 Prime 7.0000 Rest Prime 7.0000		6	Site survey (property lines, utilities, topography)	1	EA	\$ 15,000	\$ 15,000	For approx. 1 acre site
8 950 togge Perm 6 6 A 5 1000 6 60000 5 0.0000 Construction Bid comments 10 Response to contractor Bid storing bidding PPC 5 0.000 5 0.000 Construction Bid comments 0.000 Construction Bid comments 0.000 1.0000 1.000 1.000			Subtotal				\$ 90,000	
9 Find Contract Drawing - 1000 Design 0 EA 5 -2500 5 0.1027 Assume that the second control of Markon methods 11 Estimate Quantifies/Englines' Coll Estimate 1 EA 5 -3000 5 -5000 12 Specifications 1 EA 5 -3000 5 -5000 14 ESA Social Control of Markon Mith USACE and Mith Mith USACE and Mith Mith USACE and Mith Mith Mith USACE and Mith Mith Mith Mith Mith Mith Mith Mith		7						
ID Response to contractive PF advance bidding POC S DOC S DOC Source I2 Specifications 1 KA S 500 S Source I2 Specifications 1 KA S 500 S Source I2 Specifications 1 KA S 500 S Source NYSDE C to address: NYSDE C to addres:		8						
II Extense Quantities/Engineer's Cost Estimate I EA S 3,000 S 5,000 IP Specifications IP IP S 2,000 Fieldes 3 joint permit with USEC Ear IP Specifications IP IP S 2,000 S 5,000 IP IP IP IP IP S 2,000 S 5,000 IP		9		6				
Image: specifications I FA S 2,500 S 7,500 Image: specifications Image: sp		10	Response to contractor RFIs during bidding		POC	\$ 0	\$ 10,375	Assume 5% of overall design cost
Permitting & Instruction Includes a joint permit with USE and NYSGC to address: - Article 27- Tail Wellands Permit Permitting & Permitting & - Article 27- Tail Wellands Permit - Article 27- Tail Wellands - Article 27- Tail Wellands Permit - Article 27- Tail Wellands Permit - Article 27- Tail Wellands - Article 27- Tail - Article 27- Tail Wellands - Article 27- Tail - Artic		11	Estimate Quantities/Engineer's Cost Estimate	1	EA	\$ 5,000	\$ 5,000	
Permiting & single-endpoint J.S. Army Corps of Engineers Permitting 1 E.A. S S.0,000 S S S.0,000 S S S.0,000 S S S S.0,000 S S S S S S S S S S <td></td> <td>12</td> <td>Specifications</td> <td>1</td> <td>EA</td> <td>\$ 7,500</td> <td>\$ 7,500</td> <td></td>		12	Specifications	1	EA	\$ 7,500	\$ 7,500	
14 NYSDEC Stormwater Permit preparation 1 EA S 2,500 S 2,800 Acceptance Form, and NOT for SPDES General Permit And/OF Site Plan Review 15 to call Permits and/OF Site Plan Review 1 EA S 20,000 S 20,000 Construction Stateholder Engagement During Design 10 EA S 20,000 S 20,000 S 20,000 S 20,000 S 20,000 S 332,2875 Construction Construction 1038 TON S 771,564 Tomage of boulders installed 18 Rock Letty Improvements 1039,5 TON S 743 S 771,564 Tomage of boulders installed 10 Low and High Marsh Construction 30,60 Comprised of Clean Sand Fill Comprised of Clean Sand Fill Comprised of Clean Sand Fill S 13,01 S S 13,01 S S 2,376 Comprised of Clean Sand Fill Comprised of Clean Sand Fill Comprised of Clean Sand Fill S 13,00	Permitting & Engineering Design Development	13	U.S. Army Corps of Engineers Permitting	1	EA	\$ 50,000	\$ 50,000	NYSDEC to address: • Article 25- Tidal Wetlands Permit • Article 15 – Excavation & Fill in Navigable Waters with Water Quality Certification • Coastal Zone Consistency – 15 CFR Part 930 and 19 NYCRR Part 600 • NYS Office of General Services (NYSOGS) – Public Land Law, Article 6 • Essential Fish Habitat (EFH) consultation with National Marine Fisheries Service
15 Local Permis and/or Size Plan Review 1 EA S 20.000 S 20.000 Subtoils 5 40,000 5 40,000 Subtoils 5 352,873 Construction 5 771,964 Tonnage of boulders installed 18 Rock Letty Improvements 1039,5 TON 5 48 5 47,379 20 Pocket Sand & Sand Beach 170 CV7 \$ 3.83 47,379 21 GeotextEntTeiter Fabric 905 STO \$ 4.8 \$ 8,116 22 Sand/ Carvel Boat Launch Path 3.5 STO \$ 4.8 \$ 8,166 23 Sand/ Carvel Boat Launch Path 3.5 STO \$ 6.8 5 3.5 3.6 3.6 3.6 3.6 1.8 1.8 1.8 1.8 1.8 1.8 1.8 1.8 1.8 1.8 1.8 3.6 1.8 3.6.000 1.8 1.8		14	NYSDEC Stormwater Permit preparation	1	EA	\$ 25,000	\$ 25,000	Acceptance Form, and NOT for SPDES
16 Stakeholder Engagement During Design 1 EA \$ 40,000 \$ 40,000 Subto 1 100 10 100 </td <td></td> <td>15</td> <td>Local Permits and/or Site Plan Review</td> <td>1</td> <td>EA</td> <td>\$ 20,000</td> <td>\$ 20,000</td> <td></td>		15	Local Permits and/or Site Plan Review	1	EA	\$ 20,000	\$ 20,000	
Subtoted Subtoted S 332,875 Construction Costs 1039,5 TON \$ 743 \$ 771,964 Tonnage of boulders installed 18 Rock Letty Improvements 1039,5 TON \$ 743 \$ 771,964 Tonnage of boulders installed 10 Low and High Marsh Construction 3066 CVD \$ 48 \$ 8.116 20 Pocket Sand & Sand Beach 170 CVD \$ 48 \$ 8.116 21 Geotextile Filter Fairc 905 SYD \$ 11 10.186 Beanet Rock Sill areas 22 Sand / Cow Density Boulder Terrace 1678 CVD \$ 30.000 \$ 30.000 23 Sand / Cow Porty Boat Lawn Pro 120 EA \$ 168 \$ 13.84 24 Educational & Refe Balls - Law Pro 120 EA \$ 160 \$ 4.8sume 75% of excavated seliment volume can be reused on site Assume 75% of excavated seliment volume can be reused on site Assume 75% of excav		16		1	EA	\$ 40,000	\$ 40,000	
17 Rock letty improvements 103.5 TON S 77.3 S 77.1,964 Tonnage of boulders installed 18 Rock Low Sill 10.07 C/D S 4.8 S 1.47,327 Comprised of Clean Sand Fill 20 Pocket Sand & Sand Beach 1.70 C/D S 4.8 S 8,116 20 Pocket Sand & Sand Beach 1.70 C/D S 4.8 S 8,116 21 Geotextile filter Fairce 1678 C/D S 3.9 65,867 22 Sand / Gravel Boat Launch Path 35 S 1.000 S 3.000 23 Sand / Gravel Boat Launch Path 205 S S 3.000 - - 24 Educational Signage 2.0 EA S 163 S 1.08 Rating Sori Iow and High marsh areas 26 Reef Balls - Low Pro 1.00 S 3.13 S .78,27 Assume 75% of excavated sediment / 27 Remenate Balls -							\$ 352,875	
IB Rock Low Sili 1207 CVD S 39 S 47,379 19 Low and High Marsh Construction 3086 CVD S 48 S 147,327 Comprised of Clean Sand Fill 20 Pocket Sand & Sand Beach 170 CVD S 48 S 1.16 21 Geotextile Filter Fabric 905 STO S 11 S 1.0.186 Beneath Rock Sill areas 22 Sand / Gravel Boalt aunch Path 35 SVD S 68 2.376 24 Educational Signage 2 EA S 15.000 S 3.000 25 Reef Balls - Low Pro 120 EA S 16.3 1.9.84 24 Education - Spartina 2035 S S 1.13 S 78.274 28 Sediment Excavation & Relocation on Site 6079.5 CVD S 1.13 S 78.274 30 Existing Stormwater Outfall Modification 1 EA	Construction Co	osts						
IB Rock Low Sill 120 CVD S 39 S 47,379 ID Low and High Marsh Construction 3086 CVD S 48 S 147,327 Comprised of Clean Sand Fill 20 Packet Sand & Sand Beach 170 CVD S 48 S 147,327 Comprised of Clean Sand Fill 21 Geotextile Filter Fabric 905 SVD S 11 S 10,168 Bemeath Rock Sill areas 22 Sand / Gravel Boalt Aunch Path 35 SVD S 68 S 2,376 24 Educational Signage 2 EA S 1600 S 30,000 25 Reef Balls - Bay Ball 203 SVD S 13 S Rock Rearmane Vegetation - Spartina 2035 SVD S 133 S Rock Rearmane Vegetation - Spartina 2229 TON S 113 S 250,093 Assume 75% of excavated sediment volume can be aused on site 30 Existing Stormwate		17	Rock Jetty Improvements	1039.5	TON	\$ 743	\$ 771,964	Tonnage of boulders installed
20 Pocket Sand & Sand Beach 170 CV0 5 4.8 5 8.1.16 21 Geotextile Filter Fabric 905 SYD 5 1.1 5 10.186 Beneath Rock Sill areas 22 Sand / Low Density Bouder Terrace 1678 CVD 5 3.8 5 56.867 23 Sand / Low Density Bouder Terrace 1678 CVD 5 3.8 5 5.8 5 3.8 5 5 6.8 5 2.376 24 Educational Signage 2 E.4 5 1.500 5 3.8 5 6.048 Plantings for Low and high marsh areas 25 Reef Balls - Low Pro 120 E.A 5 1.03 5 .6.048 Plantings for Low and high marsh areas 26 Reef Balls - Bay Ball 120 E.A 5 .103 5 .2009 .0000 .0000 .0000 .0000 .0000 .0000 .0000 .0000 .0000 .00000 .0000 .0000 </td <td></td> <td>18</td> <td>Rock Low Sill</td> <td>1207</td> <td>CYD</td> <td>\$ 39</td> <td>\$ 47,379</td> <td></td>		18	Rock Low Sill	1207	CYD	\$ 39	\$ 47,379	
20 Pocket Sand & Sand Beach 170 CV0 5 4.8 5 8.1.16 21 Geotextile Filter Fabric 905 SYD 5 1.1 5 10.186 Beneath Rock Sill areas 22 Sand / Low Density Bouder Terrace 1678 CVD 5 3.8 5 56.867 23 Sand / Low Density Bouder Terrace 1678 CVD 5 3.8 5 5.8 5 3.8 5 5 6.8 5 2.376 24 Educational Signage 2 E.4 5 1.500 5 3.8 5 6.048 Plantings for Low and high marsh areas 25 Reef Balls - Low Pro 120 E.A 5 1.03 5 .6.048 Plantings for Low and high marsh areas 26 Reef Balls - Bay Ball 120 E.A 5 .103 5 .2009 .0000 .0000 .0000 .0000 .0000 .0000 .0000 .0000 .0000 .00000 .0000 .0000 </td <td></td> <td>19</td> <td>Low and High Marsh Construction</td> <td>3086</td> <td>CYD</td> <td>\$ 48</td> <td>\$ 147,327</td> <td>Comprised of Clean Sand Fill</td>		19	Low and High Marsh Construction	3086	CYD	\$ 48	\$ 147,327	Comprised of Clean Sand Fill
22 Sand / Low Density Boulder Terrace 1678 CYD \$ 39 \$ 65,867 23 Sand / Gravel Boat Launch Path 35 SVD \$ 68 \$ 2,376 24 Educational Signage 2 EA \$ 15,000 \$ 30,000 25 Reef Balls - Low Pro 120 EA \$ 163 \$ 11,480 26 Reef Balls - Bay Ball 120 EA \$ 163 \$ 19,584 27 Permanent Vegetation - Spartina 2035 SVD \$ 3 \$ 6,646 Plantings for low and high marsh areas 28 Sediment Excavation & Relocation on Site 6079.5 CVD \$ 113 \$ 78,274 Assume 75% of excavated sediment volume can be reused on site 30 Existing Stormwater Outfall Modification 1 EA \$ 3,000 \$ 3,000 \$ 20,001 31 Tree Plantings - Shade / Ornamental 6 EA \$ 1,600 \$ 9,600 \$ 1492,891 32 Picin table 3 EA \$ 6,000 \$ 1,900 \$ 5.001 31 Tree Plantings - Shade / Ornamental <td></td> <td>20</td> <td>Pocket Sand & Sand Beach</td> <td>170</td> <td>CYD</td> <td>\$ 48</td> <td>\$ 8,116</td> <td></td>		20	Pocket Sand & Sand Beach	170	CYD	\$ 48	\$ 8,116	
22 Sand / Low Density Boulder Terrace 1678 CYD \$ 39 \$ 65,867 23 Sand / Gravel Boat Launch Path 35 SYD \$ 68 \$ 2,376 24 Educational Signage 2 EA \$ 15,000 \$ 30,000 25 Reef Balls - Low Pro 120 EA \$ 96 \$ 11,480 26 Reef Balls - Low Pro 120 EA \$ 163 \$ 19,584 26 Reef Balls - Low Pro 2035 SYD \$ 3 \$ 6,046 Plantings for low and high marsh areas 27 Permanent Vegetation - Spartina 2035 SYD \$ 133 \$ 78,274 Assume 75% of excavated sediment volume can be reused on site 29 Removal & Disposal of Unusable Sediment / Materials 229 TON \$ 113 \$ 250,893 Assume 25% of excavated sediment / wolume can be reused on site 30 Existing Stormwater Outfall Modification 1 EA \$ 3,000 \$ 3,000 31 Tree Plantings - Shade / Ornametal 6 EA \$ 1,600 \$ 9,600 \$ 0,000 \$ 0,000 \$ 0,000		21	Geotextile Filter Fabric	905	SYD	\$ 11	\$ 10,186	Beneath Rock Sill areas
23 Sand / Gravel Boat Launch Path 35 SYD \$ 68 \$ 2,76 24 Educational Signage 2 EA \$ 15,000 \$ 30,000 25 Reef Balls - Low Pro 120 EA \$ 163 \$ 11,480 26 Reef Balls - Low Pro 2035 SYD \$ \$ 6,60 Plantings for Low and high marsh areas 27 Permenent Vegetation - Spartina 2035 SYD \$ \$ 5,00,06 Plantings for Low and high marsh areas 29 Removal & Disposal of Unusable Sediment / Materials 22229 TON \$ 113 \$ 250,893 ////////////////////////////////////		22		1678	CYD	\$ 39		
24 Educational Signage 2 EA \$ 15,000 \$ 30,000 25 Reef Balls - Low Pro 120 EA \$ 163 \$ 11,480 26 Reef Balls - Low Pro 120 EA \$ 163 \$ 19,584 27 Permanent Vegetation - Spartina 2035 SVD \$ 3 \$ 6,046 Plantings for Low and high marsh areas 28 Sediment Excavation & Relocation on Site 6079.5 CYD \$ 13 \$ 7,8,274 Assume 75% of excavated sediment volume can be reused on site 29 Removal & Disposal of Unusable Sediment / Materials 2229 TON \$ 113 \$ 250,893 30 Existing Stormwater Outfall Modification 1 EA \$ 3,000 \$ 3,000 31 Tree Plantings - Shade / Oramental 6 EA \$ 1,000 \$ 1,000 32 Frice table - Storde / Oramental 1 EA \$ 1,000 \$ 1,000								
Zonstruction Materials Reef Balls - Low Pro Removal & Disposal of Unusable Sediment / Materials 120 EA \$ 163 \$ 11,480 26 Reef Balls - Low Pro Removal & Disposal of Unusable Sediment / Materials 120 EA \$ 163 \$ 19,584 28 Sediment Excavation & Relocation on Site 6079,5 CYD \$ 113 \$ 78,274 Assume 75% of excavated sediment volume can be reused on site 30 Existing Stormwater Outfall Modification 1 EA \$ 3,000 \$ 3,000 31 Tree Plantings - Shade / Ornamental 6 EA \$ 1,000 \$ 1,000 32 Picnic table 3 EA \$ 6,600 \$ 19,800 33 Cred Mariners During Construction and for Proposed Conditions 1 EA \$ 1,000 \$ 1,000 34 Metes and Bounds Description for Easements and AS-Built Conditions 1 EA \$ 1,000 \$ 1,000 To be prepared by a licensed sureyey 35 Cont								
Construction Materials 26 Reef Balls - Bay Ball 120 EA \$ 163 \$ 19,584 27 Permanent Vegetation - Spartina 2035 SYD \$ 3 \$ 6,046 Plantings for low and high markaneas 28 Sediment Excavation & Relocation on Site 6079.5 CYD \$ 13 \$ 78,274 Assume 75% of excavated sediment volume can be reused on site 30 Existing Stormwater Outfall Modification 1 EA \$ 3,000 \$ 3,000 31 Tree Plantings - Shade / Omamental 6 EA \$ 1,000 \$ 9,000 32 Picin table 3 EA \$ 1,000 \$ 1,000 34 Metes and Bounds Description for Easements and As-Built 1 EA \$ 1,000 \$ 10,000 To be prepared by a licensed surveyor 5 Conditions S Conditions \$ 1,402,891 Assumed percentage of overall construction cost 36 Mobilization & Demobilization Poct </td <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>								
Construction Materials 27 Permanent Vegetation - Spartina 2035 SYD \$ 3 \$ 6,046 Plantings for low and high marsh areas Assume 75% of excavated sediment Assume 75% of excavated sediment volume can be reused on site 28 Sediment Excavation & Relocation on Site 6079.5 CYD \$ 13 \$ 78,274 Assume 75% of excavated sediment volume can be reused on site 29 Removal & Disposal of Unusable Sediment / Materials 2229 TON \$ 113 \$ 250,833 Assume 25% of excavated sediment volume will be disposed of offsite 30 Existing Stormwater Outfall Modification 1 EA \$ 3,000 \$ 3,000 31 Tree Plantings - Shade / Ornamental 6 EA \$ 1,000 \$ 9,600 32 Plenic table Ontractor Mariners During Construction and for Proposed 1 EA \$ 1,000 \$ 1,000 \$ 1,000 \$ 1,000 \$ 1,000 \$ 1,000 \$ 1,000 \$ 1,000 \$ 1,000 \$ 1,000 \$ 1,000 \$ 1,000 \$ 1,000 <								
Materials 28 Sediment Excavation & Relocation on Site 6079.5 CYD \$ 13 \$ 78,274 Assume 75% of excavated sediment volume can be reused on site 29 Removal & Disposal of Unusable Sediment / Materials 22.29 TON \$ 113 \$ 250.893 Assume 25% of excavated sediment volume can be reused on site 30 Existing Stormwater Outfall Modification 1 EA \$ 3,000 \$ 3,000 31 Tree Plantings - Shade / Ornamental 6 EA \$ 1,600 \$ 9,600 32 Plicnic table 3 EA \$ 6,600 \$ 19,800 \$ 1,000 \$	Construction							Plantings for low and high marsh areas
28 Sediment Excavation & Relocation on Site 6079.5 CYD \$ 13 \$ 78,27 volume can be reused on site 29 Removal & Disposal of Unusable Sediment / Materials 2229 TON \$ 1113 \$ 250,893 Assume 25% of excavated sediment volume will be disposed of offsite 30 Existing Stormwater Outfall Modification 1 EA \$ 3,000 \$ 3,000 31 Tree Plantings - Shade / Ornamental 6 EA \$ 6,600 \$ 19,800 \$ 1000 32 Picnic table 3 EA \$ 6,600 \$ 19,800 \$ 1000 34 Metes and Bounds Description for Easements and As-Built 1 EA \$ 10,000 \$ 10,000 To be prepared by a licensed surveyor continues Subtotal 1 EA \$ 10,000 \$ 10,000 To be prepared by a licensed surveyor contractor Subtotal 1 EA \$ 10,000 \$ 10,000 To be prepared by a licensed surveyor contractor Subtotal Poc							1	° °
29 Removal & Disposal of Unusable Sediment / Materials 22.29 10N \$ 113 \$ 25.083 volume will be disposed of offsite 30 Existing Stormwater Outfall Modification 1 EA \$ 3,000 \$ 3,000 31 Tree Plantings - Shade / Ornamental 6 EA \$ 1,600 \$ 9,600 32 Picnic table 3 EA \$ 6,600 \$ 10,000 \$ 10,000 34 Metes and Bounds Description for Easements and As-Built Conditions 1 EA \$ 10,000 \$ 10,000 To be prepared by a licensed surveyor Subtotal Subtotal 1 EA \$ 10,000 \$ 10,000 Subtotal 1 EA \$ 10,000 \$ 0,000 To be prepared by a licensed surveyor Subtotal Subtotal Subtotal Subtotal EA \$ 10,000 \$ 10,000 To be prepared by a licensed surveyor Subtotal Subtotal EA \$ 10,000 \$ 0,000 To be prepared by a licensed surveyor	materials	28	Sediment Excavation & Relocation on Site	6079.5	CYD	\$ 13	\$ 78,274	
31 Tree Plantings - Shade / Ornamental 6 EA \$ 1,600 \$ 9,600 32 Picnic table 3 EA \$ 6,600 \$ 19,800 33 File Notice to Mariners During Construction and for Proposed Conditions 1 EA \$ 1,000 \$ 1,000 34 Metes and Bounds Description for Easements and As-Built Conditions 1 EA \$ 10,000 \$ 10,000 To be prepared by a licensed surveyor Subtotal Subtotal Subtotal POC 6% \$ 1,492,891 Subtotal Subtotal POC 6% \$ 16,164 Assumed percentage of overall construction cost 36 Contractor Management POC POC 5% \$ 96,788 Assumed percentage of overall construction cost 37 Soil Erosion and Sediment Control During Construction POC 0.5% \$ 9,679 Assumed percentage of overall construction cost 38 Contractor Bonds & Insurance POC 0.5% \$ 38,715 Assumed								
32 Picnic table 3 EA \$ 6,600 \$ 19,800 33 File Notice to Mariners During Construction and for Proposed Conditions 1 EA \$ 1,000 \$ 1,000 34 Metes and Bounds Description for Easements and As-Built Conditions 1 EA \$ 10,000 \$ 10,000 To be prepared by a licensed surveyor Subtotal Subtotal Subtotal 36 Contractor Management POC 6% \$ 116,146 Assumed percentage of overall construction cost 36 Mobilization & Demobilization POC 5% \$ 96,788 Assumed percentage of overall construction cost 37 Soil Erosion and Sediment Control During Construction POC 2.0% \$ 38,715 Assumed percentage of overall construction cost 39 Contractor Profit POC 2.0% \$ 38,715 Assumed percentage of overall construction cost 40 Contractor Direct Expense POC 20% \$ 387,153 Assumed percentage of overall construction cost 40 Contractor Direct Expense POC 20% \$ 387,153 Assumed percentage of overall construction cost 40			-					
33 File Notice to Mariners During Construction and for Proposed Conditions 1 EA \$ 1,000 \$ 1,000 34 Metes and Bounds Description for Easements and As-Built 34 1 EA \$ 10,000 \$ 10,000 To be prepared by a licensed surveyor Subtotal EA \$ 10,000 \$ 10,000 To be prepared by a licensed surveyor Subtotal EX \$ 1,000 \$ 1,492,891 Assumed percentage of overall construction cost 36 Contractor Management POC 6% \$ 116,146 Assumed percentage of overall construction cost 37 Soil Erosion and Sediment Control During Construction POC 5% \$ 9,678 Assumed percentage of overall construction cost 38 Contractor Bonds & Insurance POC 2.0% \$ 38,715 Assumed percentage of overall construction cost 39 Contractor Direct Expense POC 2.0% \$ 38,715 Assumed percentage of overall construction cost 40 Contractor Direct Expense POC 20% \$ 387,15 Assumed percentage of overall construction cost <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>								
34 Metes and Bounds Description for Easements and As-Built Conditions 1 EA \$ 10,000 To be prepared by a licensed surveyor Subtotal Subtotal 1 EA \$ 10,000 \$ 10,000 To be prepared by a licensed surveyor Subtotal 90C \$ 1,492,891 35 Contractor Management POC 6% \$ 116,146 Assumed percentage of overall construction cost 36 Mobilization & Demobilization POC 5% \$ 96,788 Assumed percentage of overall construction cost 37 Soil Erosion and Sediment Control During Construction POC 0.5% \$ 9,679 Assumed percentage of overall construction cost 38 Contractor Bonds & Insurance POC 2.0% \$ 38,715 Assumed percentage of overall construction cost 39 Contractor Profit POC 20% \$ 387,153 Assumed percentage of overall construction cost 40 Contractor Direct Expense POC 20% \$ 387,153 Assumed percentage of overall construction cost 5 Subtotal F F 803,343 F			File Notice to Mariners During Construction and for Proposed					
35 Contractor Management POC 6% \$ 116,146 Assumed percentage of overall construction cost 36 Mobilization & Demobilization POC 5% \$ 96,788 Assumed percentage of overall construction cost 37 Soil Erosion and Sediment Control During Construction POC 0.5% \$ 9,679 Assumed percentage of overall construction cost 38 Contractor Bonds & Insurance POC 2.0% \$ 38,715 Assumed percentage of overall construction cost 39 Contractor Direct Expense POC 20% \$ 387,157 Assumed percentage of overall construction cost 40 Contractor Direct Expense POC 20% \$ 387,157 Assumed percentage of overall construction cost Subtotal POC S 387,157 Assumed percentage of overall construction cost		34	Metes and Bounds Description for Easements and As-Built	1	EA	\$ 10,000	\$ 10,000	To be prepared by a licensed surveyor
35 Contractor Management POC 5% \$ 116,146 construction cost 36 Mobilization & Demobilization POC 5% \$ 96,788 Assumed percentage of overall construction cost 37 Soil Erosion and Sediment Control During Construction POC 0.5% \$ 9,678 Assumed percentage of overall construction cost 38 Contractor Bonds & Insurance POC 2.0% \$ 38,715 Assumed percentage of overall construction cost 39 Contractor Profit POC 8.0% \$ 115,486 Assumed percentage of overall construction cost 40 Contractor Direct Expense POC 20% \$ 387,153 Assumed percentage of overall construction cost visual director Direct Expense POC POC 8.0% \$ 115,486 Assumed percentage of overall construction cost subtotal POC 8.0% \$ 154,861 Assumed percentage of overall construction cost Assumed percentage of overall construction cost			Subtotal				\$ 1,492,891	
Seneral Repts & Contractor Cost Mobilization & Demobilization POC 5% \$ 96,788 Assumed percentage of overall construction cost 36 Mobilization & Demobilization POC 5% \$ 96,788 Assumed percentage of overall construction cost 37 Soil Erosion and Sediment Control During Construction POC 0.5% \$ 99,679 Assumed percentage of overall construction cost 38 Contractor Bonds & Insurance POC 2.0% \$ 38,715 Assumed percentage of overall construction cost 39 Contractor Profit POC 8.0% \$ 154,861 Assumed percentage of overall construction cost 40 Contractor Direct Expense POC 20% \$ 387,155 Assumed percentage of overall construction cost with the temperature Subtotal Mobilization Mobilization POC 20% \$ 387,155 Assumed percentage of overall construction cost with temperature Subtotal Mobilization Mobilization Mobilization Mobilization Mobilization		35	Contractor Management	_	POC	6%	\$ 116.146	
Seneral Reqts Contractor Costs Soil Erosion and Sediment Control During Construction POC 0.5% \$ 9,679 Assumed percentage of overall construction cost 38 Contractor Bonds & Insurance POC 2.0% \$ 38,715 Assumed percentage of overall construction cost 39 Contractor Profit POC 8.0% \$ 154,861 Assumed percentage of overall construction cost 40 Contractor Direct Expense POC 20% \$ 387,159 Assumed percentage of overall construction cost 5 Source of the construction cost POC 20% \$ 387,159 Assumed percentage of overall construction cost 6 POC Source of the construction cost POC Source of the construction cost Assumed percentage of overall construction cost 6 POC Source of the construction cost Assumed percentage of overall construction cost Assumed percentage of overall construction cost 6 POC Source of the construction cost Assumed percentage of overall construction cost 7 Source of the construction cost POC Source of the construction cost 8 Source of the construction cost POC Source of the construction cost								Assumed percentage of overall
Contractor Costs 38 Contractor Bonds & Insurance POC 2.0% \$ 38,715 Assumed percentage of overall construction cost 39 Contractor Profit POC 8.0% \$ 154,861 Assumed percentage of overall construction cost 40 Contractor Direct Expense POC 20% \$ 387,153 Assumed percentage of overall construction cost U Subtotal V V \$ 803,343 V	General Reats &	37	Soil Erosion and Sediment Control During Construction		POC	0.5%	\$ 9,679	Assumed percentage of overall
39 Contractor Profit POC 8.0% \$ 154,861 Assumed percentage of overall construction cost 40 Contractor Direct Expense POC 20% \$ 387,153 Assumed percentage of overall construction cost 40 Subtotal POC 20% \$ 387,153 Assumed percentage of overall construction cost	Contractor	38	Contractor Bonds & Insurance		POC	2.0%	\$ 38,715	Assumed percentage of overall
40 Contractor Direct Expense POC 20% \$ 387,133 construction cost		39	Contractor Profit		POC	8.0%	\$ 154,861	Assumed percentage of overall
		40	Contractor Direct Expense		POC	20%	\$ 387,153	
Total Estimated 2020 Project Cost (without Contingency) \$ 2,739,109							1	
		То	otal Estimated 2020 Project Cost (without Contingency)				\$ 2,739,109	

Preliminary Design Report