

STI-P3
voltage
below
criteria

The easy scenarios Scenario 1A

Corner Gas Station with three P3 tanks

Tank 1 - Local -836mv

Remote 1 -825mv

Remote 2: -831mv

Tank 2 – Local -767mv

Remote 1 -777mv

Remote 2 -782mv

Tank 3 – Local -886mv

Remote 1 -871mv

Remote 2 -877mv



STI-P3 voltage below criteria No Isolation issues

Soil Resistivity

Current Requirement

Can you use R972 (30 milliamps)

May need CP Expert, but galvanic could be adequate

Supplemental Anodes? STI RP R972



RECOMMENDED PRACTICE FOR THE ADDITION OF SUPPLEMENTAL ANODES TO STI-P3® USTs R972

RECORD KEEPING FORM WHEN ADDING ANODES TO STI-P3® TANKS FOLLOWING STEEL TANK INSTITUTE'S RECOMMENDED PRACTICE R972 Date Anodes Added: INSTALLER INFORMATION BEFORE ANODE INSTALLATION: Tank (top view) Indicate Location and Value of All Potential Readings Tank is isolated from other metallic structures: Current Requirement Measurement (mA): Soil Resistivity: Number of Anodes Installed Weight of Each Anode: AFTER ANODE INSTALLATION: Tank (top view) Indicate Location and Value of All Potential Readings Indicate Placement, Depth and Orientation of Anodes on the Tank: Tank (top view)



STI-P3 voltage below criteria No Isolation issues

Soil Resistivity

Current Requirement

Can you use R972 (30 milliamps)

May need CP Expert, but galvanic could be adequate

Supplemental Anodes? STI RP R972





Impressed Current Below Criteria

The easy scenarios Scenario 1B

Golf Course with old, 6K gallon, bare steel tank protected with Impressed Current. Solid records of tests and rectifier readings.

Tank 1 – Local 1 – ON -1098mv INSTANT OFF -795mv

Local 2 - ON -1150mv INSTANT OFF -702mv

Local 3 – ON -945mv INSTANT OFF -845mv

Local 1 depolarized to -677mv

Local 2 depolarized to -655mv

Local 3 depolarized to -745mv

Rectifier output – 0.98 amps



Impressed Current Below Criteria

Checked continuity (real continuity not California continuity) back to rectifier negative

Check individual anode output if you can

Consult CP Expert (defined by regulation not by vibes)

The easy scenarios Scenario 1B

Golf Course with old, 6K gallon, bare steel tank protected with Impressed Current. Solid records of tests and rectifier readings.





Galvanic

And

Impressed Current

The HARD Scenarios Hard = Money Hard = Enforcement Bandwidth

Galvanic

- Not tested in 5 years ownership changes, inaccurate initial registrations, just slipped by
- Subsequent test fails with numbers that are indicative of bare steel
- Leak Detection records are less than stellar

Impressed Current

- Not tested in 6 years same old reasons
- Sketchy or anecdotal "records" of facility maintaining power
- Requested test fails; amperage seems low based on information; Inconclusive continuity back to rectifier negative
- Using Inventory Control for the past two years



Galvanic and Impressed Current

What about designed safety factors?

What do insurance records indicate?

How are USEPA's confirmed releases going?

The Gray Scenarios Have to be thoughtful to resolve

Galvanic

- Not tested in 3 years, 11 months new management, tester is overloaded
- Good history of passing records going back a decade
- Immaculate leak detection records
- Stable tank top no construction, no locality utility upgrades

Impressed Current

- Not tested in 3 years, 3 months forgot to schedule
- Decent history of CP tests
- Great 60 day rectifier log, but you notice amperage output is about 75% of last passing test
- Using SIR for last 15 years for tank and piping and it seems fine



Review critically

Do not get hung up on magic numbers and dates

Don't take "pass"

Isolation and Continuity are common errors


100mv shift is common error

ICCP "on means nothing to a tester"

Check certificates

Require good documentation

The best advice I have





Any Questions?

Steve Pollock, Technical Manager STI/SPFA spollock@stispfa.com

