

Titan Cloud

Qualitative Dry Line Test PM2 (for Rigid and Flexible Pipelines)

LINE TIGHTNESS TEST METHOD

Certification	Leak rate of 0.1 gph with PD = 100% and PFA = 0%. Leak rate of 0.025 gph with PD = 100% and PFA = 0%.
Leak Threshold	< 0.05 gph. Proprietary for dry test mode. < 0.0125 gph for leak rate of 0.025 gph.
Applicability	Any dry pipeline.
Specification	System tests fiberglass, steel and flexible pipelines. Dry Tests are conducted at 45 psi or 150% of operating pressure using the system as a digital manometer against the fluid and trapped vapor in the pipeline. Mechanical line leak detector must be removed or manually isolated from pipeline for duration of test, or if testing is to be conducted with mechanical line leak detector in place, check valve in pump must be manually closed.
Pipeline Capacity	<u>For leak rate of 0.1 gph</u> Maximum of 371.22 gallons in rigid piping. Maximum of 109.8 gallons in flexible piping. Maximum total of 481 gallons in combination rigid and flexible (the capacity of the flexible component cannot exceed 109.8 gallons). Manifolded piping may be tested as long as the total length of piping is within the capacity and configuration limitations. <u>For leak rate of 0.025 gph</u> Maximum of 165 gallons in rigid piping. Maximum of 110 gallons in flexible piping. Maximum total of 275 gallons in combination rigid and flexible (the capacity of the flexible component cannot exceed 110 gallons). Maximum pipe diameter is 6.00 inches. Manifolded piping may be tested as long as the total length of piping is within the capacity and configuration limitations.
Waiting Time	None between delivery and testing. None between dispensing and testing.
Test Period	<u>For leak rate of 0.1 gph</u> Minimum of 3 minutes after installing in line. Test data is collected continuously and recorded by computer. Data is analyzed at the Leighton O'Brien analysis center with telemetry. <u>For leak rate of 0.025 gph</u> Minimum of 5 minutes after installing in line. Test data is collected continuously and recorded by computer. Data is analyzed at the Leighton O'Brien analysis center with telemetry.
Calibration	No temperature sensors used. System must be calibrated yearly in accordance with manufacturer's instructions.
Comments	Groundwater is overcome with pressure on the top of the fluid test system apparatus during the dry test.

Titan Cloud
4015 Travis Dr , Suite 211 #1787
Nashville, TN 37211
Tel: (615) 372-6000
E-mail: roi@titancloud.com
URL: https://www.titancloud.com

Evaluator: Ken Wilcox Associates
Tel: (816) 443-2494
Date of Evaluation: 10/11/10, 06/21/2018



| [Home](#) | [Vendors: A - F](#) | [Vendors: G - M](#) | [Vendors: N - S](#) | [Vendors: T - Z](#) | [Method Index](#) | [Glossary](#) |

Appearance on this list is not to be construed as an endorsement by any regulatory agency nor is it any guarantee of the performance of the method or equipment.

Equipment should be installed and operated in accordance with all applicable laws and regulations. For full details, please refer to our expanded "[DISCLAIMER](#)" page.